



1. ASPHALT SHALL BE PLACED AND SPREAD USING A MECHANICAL PAVER.
2. ASPHALT LAYERS (AFTER ROLLING) TO BE COMPACTED TO A MINIMUM 97% S.P.M.D.D.
3. IN THE EVENT OF UNSUITABLE SUB-GRADE MATERIAL, BASE IS TO BE OVER-EXCAVATED AND BACKFILLED WITH GRANULAR 'B' COMPACTED TO 98% S.P.M.D.D.
4. ALL BACKFILL TO BE COMPACTED IN LIFTS OF 100mm.
5. ENSURE POSITIVE DRAINAGE.
6. TAMP ALL EDGES TO A FIRM 45 DEGREE BEVEL.
7. ALL DIMENSIONS ARE IN MILLIMETRES.

Barrie
STANDARD DETAIL

BOULEVARD PATHWAY

REV No.

1

DATE: OCT 2017

SCALE: N.T.S.

BSD-320

APPROVED

DATE . . . Oct 28/17 . . .

DIRECTOR OF ENGINEERING