



1. THIS DETAIL PROVIDES MINIMUM REQUIREMENTS BASED ON A TYPICAL GENERIC INSTALLATION, CONSULT MANUFACTURER INSTRUCTIONS AND REPORT DISCREPANCIES PRIOR TO INSTALLATION.
2. CONCRETE FOOTING 1200mm MINIMUM DEPTH IN SONO TUBE.
3. BASKETBALL POLE - 900mm MINIMUM DEPTH EMBEDMENT INTO FOOTING.
4. CONCRETE FOOTING TO BE 25MPa @ 28 DAYS.
5. ALL DIMENSIONS ARE IN MILLIMETRES.
6. DETAIL TO BE USED IN CONJUNCTION WITH P1291, P1292 AND P1294.



BASKETBALL NET ASSEMBLY INSTALLATION

REV No. DATE: APR 2023

2

SCALE: N.T.S.

P1293