



POLE SPECIFICATIONS:

SECTION: OCTAGONAL TAPERED
 COLOUR: BLACK ECLIPSE
 FINISH: POLISHED

NOTES:

1. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SHOWN.
2. FOR LUMINAIRE ATTACHMENT DETAILS, SEE R338.
3. POLES SHALL BE MANUFACTURED AND PLACED SO THAT HANDHOLE ORIENTATIONS ARE IN ACCORDANCE WITH OPSD 2220.01.
4. HANDHOLE WIRING CONNECTIONS TO LUMINAIRE SHALL BE MADE IN ACCORDANCE WITH OPSD 2255.020.
5. HOLE TO BE AUGURED OR "HYDRO-VACED".
6. ADD 150MM FOUNDATION OF 19MM CLEAR CRUSHED STONE, COMPACTED, TO FIRM POLE BASE SETTINGS.
7. SET POLE ENSURING BASE OF POLE IS AT FINISHED GRADE.
8. BACKFILL AND TAMP BOTTOM 450MM BEFORE FINAL PLUMBING OF POLE THEN CONTINUE TO BACKFILL.
9. USE LIMESTONE SCREENINGS FOR BACKFILL, TAMPING EVERY 150MM UP TO 200MM BELOW FINISHED GRADE.
10. TOP LAYER OF BACKFILL SHALL BE WITH 200MM TOPSOIL TO FINISHED GRADE.
11. THE CITY SHALL SUPPLY THE POLE ID PLATE(S) AND THE CONTRACTOR SHALL SUPPLY THE BLACK STAINLESS STEEL MOUNTING NECESSARY FOR MOUNTING. THE CONTRACTOR SHALL CO-ORDINATE THE SUPPLY OF THE POLE ID PLATE(S) WITH THE CITY OF BARRIE'S TRAFFIC SERVICES DEPARTMENT. POLE ID PLATE(S) SHALL BE INSTALLED AS PER THE CONTRACT DRAWING AND AS DIRECTED BY THE CONTRACT ADMINISTRATOR IN CONSULTATION WITH TRAFFIC SERVICES.
12. POLE ID PLATE(S) SHALL BE MOUNTED HIGHER IF THE VIEW OF THE PLATE IS OBSTRUCTED.



**DECORATIVE CONCRETE POLE
 DIRECT BURIED (8.4m)**

REV No.	DATE: APR 2024
5	SCALE: N.T.S.

R339