

- Tracer wire to be installed as per the City's Tracer Wire Infrastructure Standards.
- 2. Hydrant test station conduit shall be a minimum of 25mm installed to a depth of 600mm below grade.
- 3. All connections must be waterproofed.
- 4. Splicing of tracer wire is not allowed unless specified or approved.
- 5. Heat shrink is to be completed by a heat gun and not using an open flame.
- 6. SnakePits are to be placed inside of a 5SL road leveler with lid.



Water Infrastructure **Tracer Wire**

REV No. DATE: APR 2024 6 SCALE: N.T.S

W515