

Geotechnical Investigation

Proposed Hewitt's South Residential Subdivision

Barrie, Ontario

Submitted to:

Hansen Group Inc. 35 Worsley Street Barrie, ON L4M 1Z7

Submitted by:

GEI Consultants Ltd. 647 Welham Road, Unit 14 Barrie, Ontario, L4N 0B7 www.canada.geiconsultants.com

December 18, 2023 Project No. 2304675 Revision 1

Table of Contents

1.	Intro	1	
2.	Procedures and Methodology		2
3.	Subs	3	
	3.1	General Overview	3 3
	3.2	Stratigraphy	3
	3.3	Groundwater	5
4.	Engir	neering Design Parameters & Analysis	7
	4.1	Site Grading	7
	4.2	Foundation Design	8
	4.3	Seismic Site Classification	11
	4.4	Earth Pressure Design Parameters	12
	4.5	Floor Slabs	13
	4.6	Drainage	13
	4.7	Site Servicing	14
	4.8	Pavement Design	15
	4.9	Stormwater Management Pond	18
	4.10	Infiltration Considerations	19
5.	Cons	tructability Considerations	20
	5.1	Excavations	20
	5.2	Temporary Construction Groundwater Control	21
	5.3	Compaction Specifications	21
	5.4	Quality Verification Services	22
	5.5	Site Work	23
6.	Limitations and Conclusions		24
	6.1	Limitations	24
	6.2	Conclusion	25

Figures

- 1. Site Location Plan
- 2. Borehole Location Plans
 - A. Aerial Image
 - B. Proposed Site Plan



Appendices

- A. Borehole Logs
- B. Geotechnical Laboratory Data
- C. Previous Borehole Information
- D. Typical Details



1. Introduction

GEI Consultants Ltd. (GEI) was retained by Hansen Group Inc (Client) to complete a geotechnical investigation and report for the Proposed Hewitt's South Residential Subdivision in Barrie, Ontario. A site location plan is enclosed as Figure 1.

The southern portion of the Hewitt's Residential Subdivision is planned for construction. The area slated for development is just north of Lockhart Road. The site is currently undeveloped agricultural land. A mixed residential development is planned with several 6 to 8 storey buildings with a single level of underground parking, townhomes and single lots. A small commercial block is proposed in the southeast corner of the site. A large Storm Water Management (SWM) facility is planned of the western part of the site. A network of paved roads will connect the site and it is understood that the subdivision will have full municipal servicing. The concept plan is shown in Figure 2B and may undergo some revisions as the design progresses. An aerial image of the site is shown in Figure 2A.

A previous preliminary geotechnical report was prepared by others and provided for GEI's review. The relevant borehole information is appended for completeness.

The purpose of the geotechnical investigation was to assess the subsurface soil conditions at the site, and based on this information, provide geotechnical engineering recommendations in support of the proposed development. This report summarizes the borehole findings, provides design geotechnical engineering recommendations regarding available bearing capacities for foundations, site grading and earthworks, floor slabs, earth pressure coefficients for basements, drainage requirements, site servicing installation, SWM pond, infiltration and pavement design. Considerations for constructability such as soil excavation, compaction, on-site backfill suitability and temporary groundwater control are also provided.

It is noted that the recommendations provided in this report must be considered preliminary in nature due to the current uncertainty of the design for the project. As the design progresses further geotechnical review and input may be required which might necessitate the need for additional investigation and/or analysis.

1

2. Procedures and Methodology

It is noted that all elevations in this report are metric/geodetic and expressed in metres (m). All measurements are also in metric and expressed in millimetres (mm), metres (m) or kilometres (km).

Prior to the commencement of drilling activities, the borehole locations were staked in the field by GEI. Ground surface elevations of the boreholes and horizontal co-ordinates (referencing NAD 83 geodetic datum) were surveyed by GEI with a Topcon FC – 5000 GPS Survey unit.

Underground utilities including natural gas, electrical, telephone, water, etc. were marked out by public and private utility locating companies prior to drilling.

The fieldwork for the drilling program was carried out between November 2 and 8, 2023. Boreholes 1 to 29 were advanced to 6.6 m below existing grade (Elev. 245.2 to 257.1) across the site. Borehole logs are provided in Appendix A and the borehole locations are shown on Figures 2A and 2B.

The boreholes were advanced by a drilling subcontractor retained and supervised by GEI using a track-mounted drill rig, solid stem augers, and standard soil sampling equipment. Sampling was conducted using a 51 mm O.D. Split Spoon (SS) sampler. Standard Penetration Test (SPT) "N" Values (N values) were recorded for the sampled intervals as the number of blows required to drive an SS sampler 305 mm into the soil using a 63.5 kg drop hammer falling 750 mm, in accordance with ASTM D1586. In each borehole soil sampling was conducted at 0.75 m intervals for the upper 3.0 m and at 1.5 m intervals thereafter.

Monitoring wells were installed in Boreholes 1, 2, 5, 6, 9, and 11 to 21 by GEI to facilitate long-term groundwater monitoring, each consisting of 50 mm diameter PVC pipe with a 1.5 m long screen and protective casing. Monitoring well construction is shown on the borehole logs in Appendix A. Boreholes without wells were backfilled in accordance with O.Reg. 903.

The GEI field staff examined, and classified characteristics of the soils encountered in the boreholes, including the presence of fill materials, groundwater observations during and upon completion of the drilling, recorded observations of borehole construction, and processed the recovered samples. All recovered soil samples were logged in the field, carefully packaged, and transported to GEI's laboratory for more detailed examination and classification.

In GEI's laboratory, the samples were classified as to their visual and textural characteristics. A total of fourteen (14) representative samples of the major soil units were selected and submitted to our laboratory for grain size analysis. Three (3) of the samples were also submitted for Atterberg Limits tests. Laboratory results are provided in Appendix B.



2

3. Subsurface Conditions

3.1 General Overview

The detailed soil profiles encountered in the boreholes are indicated on the attached borehole logs in Appendix A, and the geotechnical laboratory results are included in Appendix B. The borehole locations are shown in Figures 2A and 2B.

It should be noted that the conditions indicated on the borehole logs are for specific locations only and can vary between and beyond the locations. It should be noted that the soil boundaries indicated on the borehole logs are inferred from non-continuous sampling and observations during drilling. These boundaries are intended to reflect approximate transition zones and should not be interpreted as exact planes of geological change.

In addition, the descriptions provided in the borehole logs are inferred from a variety of factors, including: visual observations of the soil samples retrieved, laboratory testing, measurements prior to and after drilling, and the drilling process itself (speed of drilling, shaking/grinding of the augers, etc.). The passage of time also may result in changes in conditions interpreted to exist at locations where sampling was conducted.

3.2 Stratigraphy

3.2.1 Topsoil

A topsoil layer was at the ground surface in all boreholes ranging in thickness from 50 to 760 mm, typically 100 to 305 mm. Topsoil thickness may vary between boreholes and in other areas of the site.

3.2.2 Fill

A fill layer was encountered in most boreholes (Boreholes1, 2, 4 to 10, 12, 13, 15 to 17, 20, 24 to 27, and 29) below the topsoil and considered to be associated with the agricultural activities and disturbance of the in-situ soil over time. The fill was penetrated at 0.8 m depth, locally 1.5 m depth, (Elev. 251.0 to 262.9). The fill predominantly consisted of silty and or sand, with trace gravel, locally varying to clayey silt or sandy silt. Trace organics were observed in most boreholes. The fill was moist with moisture contents of 3 to 32%. The fill typically had N values of 10 or less revealing loose conditions, locally firm/stiff or compact.

3.2.3 Upper Sand/Silty Sand/Fine Sand/Gravelly Sand

Underlying the fill or topsoil, upper discontinuous layers of sand/silty sand/fine sand or gravelly sand were revealed in Boreholes 1, 2, 6, 8, 11, 14 to 21, 23, 24 and 27 to 29. The upper



GEI Consultants 3

cohesionless soil layers were penetrated at depths of 0.8 to 4.6 m (Elev. 252.5 to 260.5), typically 1.5 to 2.3 m depth. The N values in these layers ranged between 4 and 59 blows, indicating loose to very dense conditions, but typically being loose to compact. The layers were moist to wet with depth, with moisture contents ranging between 1 and 36%.

3.2.4 Silty Clay

A silty clay layer was revealed in Boreholes 3 to 7, 13, 17, 18, 20, 22 to 24, and 26. In Boreholes 3 to 7, 13, 17 and 22 to 24 the layer was typically thinner and was revealed in the upper part of the boreholes from 0.2 to 2.3 m depth (Elev. 250.3 to 256.1) and being penetrated at 1.5 to 4.6 m depth (Elev. 247.2 to 255.4). In Boreholes 18, 20 and 26, the silty clay layer was slightly thicker and was revealed at depth, from 4.6 m depth (Elev. 255.0 to 257.2) and extending to 6.1 m depth (Elev. 253.5 to 254.2) in Boreholes 18 and 26, and to the 6.6 m depth of exploration (Elev.255.2) in Borehole 20. Three (3) samples of the material were submitted for grain size analysis and the results are provided in Figure B1 in Appendix B. All three (3) samples were also submitted for Atterberg Limit tests and the results are presented on Figure B5 in Appendix B. Plastic limits of 20.4 to 23.8 and liquid limits of 45.1 to 50.3 were revealed from the lab testing. The soil was moist to wet with moisture contents of 15 to 45%. The consistency was firm to hard with blow counts of 5 to 30.

3.2.5 Clayey Silt

A local layer of clayey silt was underlying the fill in Boreholes 12 and 25 and extending to 1.5 m depth (Elev. 250.9 to 254.1). The unit had trace to some sand and trace gravel. The soil had a firm to stiff consistency with N values of 7 and 11. Moisture contents were 20 and 36%.

3.2.6 Sand and Silt/Silt and Sand

A unit of sand and silt/silt and sand was present in Boreholes 3 to 5, 7, 9, 10, 18 to 21, 26 and 28. The unit varied in thickness from 0.7 to 5.3 m and occurred from 0.6 to 3.0 m depth (Elev. 251.0 to 260.5) and terminated at 1.5 to 6.1 m depth (Elev. 249.2 to 257.5). Trace clay was noted in most samples. Two (2) samples of the material were submitted for grain size analysis and the results are provided in Figure B2 in Appendix B. The soil was moist to wet with depth and moisture contents were 2 to 36%. The soil was typical compact, locally loose or dense, with N values ranging from 6 to 34.

3.2.7 Glacial Till

A major glacial till deposit was encountered in all boreholes, except Boreholes 20, 21 and 27, below the upper soil layers. The till extended to the 6.6 m depth of exploration (Elev. 245.2 to 256.6) in Boreholes 4, 5, 7, 9, 10 to 12, 15 to 19, 22, 24, 26, 28 and 29. In Boreholes 1 to 3, 6, 8, 13, and 23, the till was penetrated at 4.6 to 6.1 m depth (Elev. 247.0 to 251.7). Locally in Boreholes 14 and 25 the till was interrupted between 3.0 and 4.6 m depth (Elev. 249.4 to 251.0)



by a sand layer and 4.6 to 5.0 m depth (Elev. 250.5 to 251.0) by a gravelly sand layer, respectively. The till matrix varied between a silty and sandy silt with trace to some clay and gravel. Cobbles and boulders should be expected based on augers grinding during advancement of the boreholes. Six (6) samples of the material were submitted for grain size analysis and the results are provided in Figures B3 in Appendix B. The glacial till was brown, locally grey at depth, and was typically moist to wet with depth with local wet seams. Moisture contents were 7 to 24%. N values in the glacial till ranged from 6 to more than 100 blows, indicating loose to very dense conditions, typically being compact.

3.2.8 Lower Sand/Gravelly Sand

Basal sand/gravelly sand deposits were noted at the base of Boreholes 1 to 3, 6, 8, 13, 14, 21, 23, 25 and 27 extending beyond the 6.6 m depth of the boreholes (Elev. 246.5 to 257.0). Locally in Boreholes 14 and 25, a sand or gravelly sand layer interrupted the till between 3.0 and 4.6 m depth (Elev. 249.4 to 251.0) and 4.6 to 5.0 m depth (Elev. 250.5 to 251.0), respectively. Two (2) samples of the material were submitted for grain size analysis and the results are provided in Figure B4 in Appendix B. The soil was typically wet with moisture contents of 8 to 21%. N values in the layers were 17 to more than 100, indicating compact to very dense soil, typically showing dense to very dense soil.

3.3 Groundwater

Unstabilized groundwater level measurements and cave measurements were taken upon the completion of drilling of each borehole as shown on the borehole logs in Appendix A. These measurements were taken to provide a rough estimate of the possible excavation and temporary groundwater control constructability considerations that may arise. Sixteen (16) boreholes were outfitted with a monitoring well with 50 mm diameter PVC standpipe and 1.5 m long screen. Monitoring well configuration and groundwater observations are noted on the borehole logs in Appendix A, and a summary is below.

Borehole	Depth of Cave (m) / Elev.	Unstabilized Groundwater Level Depth / Elev.	Depth / Elev. of Groundwater Table, Nov. 29, 2023
1	Open (6.6 / 249.8)	No Water	0.5 / 255.8
2	3.3 / 252.8	2.3 / 253.8	0.4 / 255.7
3	Open (6.6 / 248.8)	3.3 / 252.0	N/A
4	Open (6.6 / 245.2)	No Water	N/A
5	Open (6.6 / 251.1)	No Water	1.8 / 255.8
6	Open (6.6 / 248.7)	5.4 / 249.8	1.2 / 254.0
7	Open (6.6 / 249.1)	3.0 / 252.7	N/A
8	4.2 / 252.1	3.0 / 253.3	N/A



Borehole	Depth of Cave (m) / Elev.	Unstabilized Groundwater Level Depth / Elev.	Depth / Elev. of Groundwater Table, Nov. 29, 2023
9	2.0 / 256.0	1.9 / 256.1	1.3 / 256.7
10	4.0 / 255.8	1.8 / 258.0	N/A
11	Open (6.6 / 256.1)	No Water	3.9 / 258.7
12	Open (6.6 / 245.8)	2.4 / 250.0	Pipe Blocked
13	Open (6.6 / 246.5)	No Water	Pipe Blocked
14	4.5 / 249.5	3.5 / 250.5	1.2 / 252.8
15	5.8 / 249.8	5.1 / 250.5	2.1 / 253.5
16	Open (6.6 / 249.4)	No Water	2.1 / 253.9
17	Open (6.6 / 250.5)	5.8 / 251.3	3.0 / 254.1
18	4.0 / 255.6	3.0 / 256.6	2.0 / 257.6
19	4.4 / 254.9	1.2 / 258.1	1.7 / 257.6
20	3.0 / 258.1	4.5 / 257.3	3.4 / 258.4
21	3.0 / 260.6	4.8 / 258.8	5.4 / 258.2
22	Open (6.6 / 246.5)	No Water	N/A
23	4.8 / 250.1	2.7 / 252.2	N/A
24	Open (6.6 / 250.0)	5.8 / 250.8	N/A
25	4.1 / 251.5	1.8 / 253.8	N/A
26	3.6 / 256.7	3.3 / 257.0	N/A
27	3.3 / 258.6	3.3 / 258.6	N/A
28	4.1 / 259.1	3.8 / 259.4	N/A
29	5.3 /258.4	5.1 / 258.6	N/A

The stabilized groundwater levels in the monitoring wells are typically within about 2 m of the ground surface corresponding to Elev. 252.8 to 258.7. This is believed to reflect a combination of perched water in the upper soil units, wet seams or wet cohesionless layers in the till deposit and groundwater under sub-artesian pressure in the lower sand/gravelly sand unit below the till.

The silty clay and clayey silt are not permeable. The till, silt and sand/sand and silt and fine sand units are semi permeable. The sand, silty sand and gravelly sand are permeable.

Groundwater levels are expected to show seasonal fluctuations and vary in response to prevailing climate conditions.

4. Engineering Design Parameters & Analysis

The southern portion of the Hewitt's Residential Subdivision is planned for construction. The area slated for development is just north of Lockhart Road. The site is currently undeveloped agricultural land. A mixed residential development is planned with several 6 to 8 storey buildings with a single level of underground parking, townhomes and single lots. A small commercial block is proposed in the southeast corner of the site. A large Storm Water Management (SWM) facility is planned of the western part of the site. A network of paved roads will connect the site and it is understood that the subdivision will have full municipal servicing. The concept plan is shown in Figure 2B and may undergo some revisions as the design progresses. An aerial image of the site is shown in Figure 2A.

In general, the current preliminary design is feasible with geotechnical engineering recommendations to be confirmed once design details have been established. As the design progresses further geotechnical review and input may be required which might necessitate the need for additional investigation and/or analysis. GEI will be a part of the design team/process and review the various elements of the design for geotechnical requirements for detailed and site plan design. It is noted that the recommendations provided in this report must be considered preliminary in nature due to the current preliminary nature of the design for the project.

4.1 Site Grading

Grading plans for the site were being designed at the time of this report and it is understood that some site grading may be required to accommodate the project. When grading is established, it is understood that GEI will be a part of the process and will review the drawings for geotechnical requirements.

In general, where grades need to be raised under structures, the topsoil and fill and any localized areas of weak native soil directly below the fill/topsoil are unsuitable to support the buildings due to concern with settlement. In this regard, it is recommended to strip the topsoil and stockpile separately then sub-excavate the fill and any or upper weak native soil down to competent native soil (subject to geotechnical review during construction). The exposed competent native soil should be thoroughly compacted and then engineered fill placement can commence, to the desired grade. Footings and floor slabs would be supported by native soil and/or the engineered fill.

4.1.1 Engineered Fill

GEI defines "engineered fill" as material that will support foundations, and which is placed and compacted in a specified and controlled manner under full-time supervision of geotechnical engineering staff.



7

In any location where engineered fill will be placed to raise grades or replace poor/weak soil, the topsoil, vegetation, weathered/disturbed or existing earth fill must be fully removed down to competent native soil. The exposed subgrade soil must be proof-rolled and inspected by the geotechnical engineer to ensure all unsuitable material (e.g., organics, weak or soft soil, weathered / disturbed soil, deleterious materials, existing fill) is removed from the engineered fill footprint. Any unsuitable areas must be further sub-excavated and replaced with fill compacted to targeted 100% Standard Proctor Maximum Dry Density (SPmdd), minimum 98% SPmdd in building areas and 95% SPmdd in road and servicing areas.

Once the subgrade is approved, engineered fill can be placed. Engineered fill must be placed under the full-time supervision of a geotechnical engineer as required in the Ontario Building Code. The engineered fill may consist of excavated on-site inorganic cohesionless soils provided they have been moisture conditioned to a moisture content within 2% of optimum moisture content and do not contain organics, topsoil or deleterious material. It is recommended that any imported soil consist of Granular B (OPSS.MUNI 1010) and be first used in building areas, with suitable on-site soil used in landscaped or road areas. Engineered fill must be placed in loose lifts of 200 mm or less and compacted as noted above.

In wet subgrade areas, the first lift of engineered fill shall consist of 400 mm of Granular B Type II (OPSS.MUNI 1010). This will help to bridge the weaker subgrade and improve the ability to achieve the compaction specifications for subsequent engineered fill lifts.

The engineered fill must extend a minimum of 1 m out from all sides of the foundations and extend at a 1 horizontal to 1 vertical slope (1H:1V) down to the exposed subgrade. A typical detail for engineered fill pad dimensioning is included in Appendix C.

4.2 Foundation Design

4.2.1 Foundations on Native Soil

Grading plans for the site were being designed at the time of this report. The underground parking levels and residential basements are anticipated to extend about 3 to 4 m below the proposed grade.

Foundations at this site may be constructed as conventional spread and strip footing foundations that bear on the native, undisturbed soil in the upper 3 to 4 m of the existing ground surface as provided below. The geotechnical reaction at Serviceability Limit State (SLS) is for 25 mm or less of total settlement, and the factored geotechnical resistance at Ultimate Limit State ULS are provided in the table below for the corresponding depths and soil strata. The table below lists only the boreholes in building areas.

Borehole	Depth (m) / Elev. for Footings (At or Below)	Soil	Serviceability Limit State (SLS) (kPa)	Ultimate Limit State (ULS) (kPa)
1	2.3 / 254.0	Till	200	300
'	3.0 / 253.3	Till	300	450
2	1.5 / 254.5	Till	150	225
2	3.0 / 253.1	Till	250	375
5	0.8 / 256.9	Sand and Silt/Silty Clay/Till	100	150
6	0.8 / 233.1	Silty Sand/Silty Clay	100	150
0	2.3 / 253.0	Till	200	300
11	0.8 261.8	Sand/Gravelly Sand	200	300
12	1.5 / 250.9	Till	150	225
12	2.3 / 250.1	Till	300	450
13	2.3 / 250.8	Till	100	150
4.4	1.5 / 252.5	Till	200	300
14	3.0 / 251.0	Sand	300	450
	0.8 / 254.9	Silty Sand	100	150
15	1.5 / 254.1	Till	150	225
	3.0 / 252.6	Till	300	340
	0.8 / 255.2	Silty Sand	100	150
16	2.3 / 253.7	Till	200	300
	3.0 / 253.0	Till	300	450
17	17 0.8 / 256.3 Silty Sand/Sand/Silty Clay		50	75
18	18 0.8 / 258.8 Fine Sand/Sand and Silt		150	225
40	0.8 / 258.8	Fine Sand/Sand and Silt	150	225
19	3.0 / 256.3	Sand and Silt	300	450
-	0.8 / 261.0	Gravelly Sand	300	450
20	2.3 / 259.5	Sand/Silt and Sand	200	300
21	1.5 / 252.1	Sand	150	225



Borehole	Depth (m) / Elev. for Footings (At or Below)	Soil	Serviceability Limit State (SLS) (kPa)	Ultimate Limit State (ULS) (kPa)
22	1.5 / 251.5	Till	150	225
22	3.0 / 250.0	Till	300	450
23	1.5 / 253.4	Till	100	150
25	3.0 / 251.9	Till	200	300
24	0.8 / 255.8	Fine Sand/Silty Clay	100	150
25	1.5 / 254.1	Till	100	150
25	2.3 / 253.3	Till	300	450
26	1.5 / 259.5	Silt and Sand	100	150
27	0.8 / 261.1	Gravelly Sand/Sand	200	300
28	0.8 / 262.4	Sand	100	150
20	1.5 / 261.7	Sand/Sand and Silt	200	300
29 0.8 / 262.9 Gravelly Sand/Sand		150	225	

Locally higher bearing resistances are available or available at depth and can be provided upon request. Although, it is noted that greater groundwater control will be required during construction.

4.2.2 Foundations on Engineered Fill

If the foundations are supported on an engineered fill pad, constructed as discussed in Section 4.1.1, the spread or strip footings can be designed using the underlying native soil bearing capacity shown above, up to a maximum of 150 kPa at SLS and 225 kPa at ULS.

It is recommended that nominal reinforcing steel for stiffening of the foundation walls made on engineered fill be provided to help mitigate minor cracking due to minor differential settlement. The reinforcing steel in the poured concrete foundation walls may consist of 2-15M bars continuous at the top of the foundation wall, and 2-15M bars continuous at the bottom of the foundation walls. Typically, these bars are placed 100 to 200 mm from the top or bottom of the foundation wall, respectively. The reinforcing steel should extend a minimum of 3 m past any transition zones between engineered fill and native soil. A typical reinforcing steel detail for foundation walls placed on engineered fill is provided within Appendix C. The recommended nominal reinforcing steel should not be considered a structural design. The need for different or additional reinforcement should be reviewed by a structural engineer to ensure the original structural design intent of the structure is maintained.

4.2.3 General Foundation Considerations

All footings exposed to ambient air temperature throughout the year must be provided with a minimum of 1.2 m of earth cover or equivalent insulation for frost protection (25 mm of polystyrene insulation is equivalent to 300 mm of soil cover). The minimum strip and spread footing widths to be used shall be dictated as per the Ontario Building Code, regardless of loading considerations. Footings stepped from one level to another must be at a slope not exceeding 7V:10H.

The foundation design parameters provided above are predicated on the assumption that the foundation subgrade surface is undisturbed, and that all earth fill, deleterious, softened, disturbed, organic, and caved material is removed. The foundation excavation must be done in such a way that groundwater is controlled to prevent any disturbance to the foundation base. The groundwater table must be lowered at least 1 m below the founding elevation prior to excavation to prevent disturbance to the foundation subgrade from groundwater seepage.

The foundation subgrade must be reviewed prior to concrete placement to ensure the foundation design parameters provided are applicable, and to provide remedial recommendations if necessary. If the foundation excavation will be open for a prolonged period of time, the foundation subgrade should be protected with a skim coat of lean mix concrete (applied immediately after inspection by the geotechnical engineer), to ensure that no deterioration will occur due to weather effects.

4.3 Seismic Site Classification

Section 4.1.8.4 of the Ontario Building Code provides values of the acceleration and velocity-based site coefficients (F_a and F_v) for various time periods, associated with specific Site Classes. These Site Classes are based on the energy-corrected Average Standard Penetration Resistance values and undrained shear strength within the upper 30 m of soil underlying the grade beams or foundations of the proposed structure. As the boreholes were advanced less than this depth at the site, the site classification recommendation provided below assumes that the soil conditions are similar below the drilled depth.

Underneath the proposed foundations, the subsoil will consist of generally compact to dense cohesionless soils. The Site Classification for Seismic Site Response is "D" for this site.

4.4 Earth Pressure Design Parameters

Basement/underground parking levels or other retaining type walls must be designed to resist unbalanced lateral earth pressures imparted from the weight of adjacent soils. Lateral earth pressures are calculated using the following equation:

$$P = K[\gamma h + q]$$

where, P = the horizontal pressure at depth, h(m)

K = the earth pressure coefficient (dimensionless)

h = depth below ground surface (m)

 γ = the bulk unit weight of soil, (kN/m³)

 $\mathbf{q} = \text{surcharge loading (kPa)}$

The above equation assumes that a drainage system is present which prevents the build-up of any hydrostatic pressure behind the structure subjected to the unbalanced lateral earth pressures. If this is not the case, the equation must be revised to also incorporate the submerged unit weight of the soil multiplied by the earth pressure coefficient, in addition to the water pressure itself.

The values for use in the design of the walls subjected to unbalanced lateral earth pressures in the upper 3 to 4 m of the site are as follows:

Soil Type	γ - Bulk Unit Weight	φ - Friction	Earth Pressure Coefficient (dimensionless)		
	(kN/m³)	Angle (degrees)	K _a - Active K _o - At-Rest K _p - Passive		
Granular 'B' (OPSS 1010)	21.0	32	0.31	0.47	3.25
Compact to Very Dense Native Soil	20.0	30	0.33	0.50	3.00
Fill/Loose Native soil	19.0	28	0.36	0.53	2.77

The calculation of the earth pressure coefficients is based on Rankine theory, which provides a conservative estimate as no friction between the soil and the structure is accounted for. The earth pressure coefficients provided above are applicable for flat ground surfaces beyond the structure and must be revised for sloping ground surfaces.

The earth pressure coefficients referenced within the above table are a function of the friction angle of the adjacent soil, and both the degree and direction of movement of the structure subjected to unbalanced lateral earth pressures. For structures that are restrained at the top (such as basement walls), the at-rest earth pressure coefficient will apply. For structures that allow for 0.1 to 1% of movement away from the soil (such as unrestrained retaining walls), the

full active earth pressure coefficient will apply. For structures that allow for 1 to 10% of movement into the soil, the full passive earth pressure coefficient will apply. The percentage movement is based on the height of the structure.

Other types of structures such as shoring walls with multiple rows of tiebacks and soil nail walls are subject to different loading conditions and must be analyzed separately.

4.5 Floor Slabs

The native soils or engineered fill are suitable to support the parking garage floor slabs or basement slabs for residences.

The engineered fill pad or exposed native soil may have been loosened/disturbed and the floor slab subgrade must be proof-rolled and inspected by the geotechnical engineer. If any soft or weak subgrade areas are identified, or if there are areas containing excessive amounts of deleterious/organic material, they must be locally sub-excavated and backfilled with Granular B Type I (OPSS.MUNI 1010) placed in maximum 200 mm thick loose lifts and compacted to a minimum of 98% SPmdd within 2% optimum moisture content.

All building floor slabs must be provided with a capillary moisture barrier and drainage layer. This is made by placing the concrete slab on a minimum 200 mm layer of 19 mm clear stone (OPSS.MUNI 1004) compacted by vibration to a dense state. The upper 50 mm of clear stone can be replaced with 19 mm crusher run limestone for a working surface. The clear stone and a cohesionless subgrade must be separated by a geotextile such as Terrafix 270R (or approved equivalent) to prevent the migration of fines into the clear stone layer which could result in loss of support for the slab. Alternatively, Granular A (OPSS.MUNI 1010) can used, compacted to 100% SPmdd, without geotextile.

4.6 Drainage

For underground parking, all foundation walls must be provided with damp-proofing provisions in conformance to the Ontario Building Code. Backfill along the foundation wall must consist of Granular B Type I (OPSS.MUNI 1010) for a minimum lateral distance of 600 mm out from the foundation wall. Alternatively, if a filtered cellular drainage media is provided adjacent to the foundation wall, the backfill may consist of common earth fill.

For underground structures, a perimeter drainage system must be installed that will remove any water that infiltrates into the building backfill, to ensure that any water does not infiltrate into the basement. The perimeter drains must consist of minimum 100 mm diameter perforated pipes wrapped in filter socks, sufficiently covered on all sides by 19 mm clear stone. Perimeter drains should be directed to the sump underneath the basement floor in solid pipes so as not to surcharge the underfloor drainage layer with water. It is recommended that basements be established a minimum of 1.0 m above the groundwater level. Where basements are less than

1.0 m but 0.5 m or more above the groundwater perforated subfloor drainage pipes at 5 m centres, surrounded by 19 mm clear stone, surrounded by a geotextile such as Terrafix 270R (or approved equivalent) to prevent the migration of fines, and trenched into the subgrade is also recommended for the buildings along the short axis of the buildings. All sump pumps should be on emergency power for redundancy in case of a power outage. A typical basement drainage detail is included in Appendix C.

For new structures that will be slab-on-grade with no basement levels, perimeter and underslab drainage at the foundation level is not required, provided that the underside of concrete slab is at least 200 mm above the prevailing grade of the site and the surrounding surfaces slope away from the building at a gradient of at least 2% to promote surface water run-off and to reduce groundwater infiltration adjacent to foundations. To minimize infiltration of surface water, the upper 150 mm of backfill could consist of less permeable, compacted soil such as clayey silt at the site.

4.7 Site Servicing

It is expected that the proposed development will be serviced with municipal water, sanitary and storm sewers. Inverts were assumed to extend as deep as 3 to 4 m below the existing grade for the purposes of this report.

4.7.1 Bedding

The type of material and depth of granular bedding below the pipe will, to some extent, depend on the method of construction used by the contractor. Pipe bedding for flexible pipes should follow the requirements in Ontario Provincial Standard Drawing 802.010 or applicable municipal standards. Pipe bedding for rigid pipes should follow the requirements in Ontario Provincial Standard Drawings 802.030 to 802.032 or applicable municipal standards.

A subgrade consisting of the native soil or engineered fill will provide adequate support for pipes with the bedding requirements as laid out in the above referenced OPS drawings. Where disturbance of the trench base has occurred from groundwater seepage, construction traffic, etc., or if in-situ fill is present at the invert level, the material should be sub-excavated and replaced with suitably compacted granular fill. If weak zones are encountered, additional bedding materials and differing construction practices may be required and should be determined during construction. Any zones of organic soil should be sub-excavated and replaced with approved earth fill or imported granular material compacted to 95% SPmdd. Details on temporary groundwater control are provided in Section 5.2.

Regardless of whether flexible or rigid pipes are implemented, granular bedding and cover material should consist of a well graded, free draining material, such as Granular "A" (OPSS.MUNI 1010). All granular bedding must be compacted to a minimum of 95% SPmdd.

4.7.2 Backfill

Excavated native inorganic cohesionless soil may be re-used as backfill in trenches, provided it is moisture conditioned so that the moisture content is within 2% of optimum. Additional soil compaction details are provided in Section 5.3. The backfill should be compacted to a minimum of 95% SPmdd. In confined areas the layer thickness will have to be reduced to utilize smaller compaction equipment efficiently or by using granular material instead of locally sourced fill. Any backfill that is frozen, contains a high percentage of organic material (topsoil, peat, etc.) or moisture, or has otherwise unsuitable deleterious inclusion should not be used as backfill. The maximum cobble or boulder size should not exceed half of the loose lift thickness (i.e., all particles with a diameter greater than 100 mm should be removed). Where cohesive soils are utilized as backfill a sheepsfoot compactor will be required. In general, excavated clayey soil from the site is not recommended for re-use as backfill because these soils have moisture contents above optimum. Reducing moisture in the cohesive soil is not practical and the compaction specifications cannot be achieved.

Where trenches are within the traveled portions of a roadway, backfill within the frost penetration depth of 1.2 m should consist of native, non-organic, excavated material consistent with the soils surrounding the trench. If this technique is not undertaken, then frequently problems arise with yearly differential frost heave movements between the trench backfill and the adjacent native soil. This would occur, for example, if imported granular material is used to backfill trenches which is less susceptible to frost effects compared to the native soils on site. Alternatively, if different soil is used as the backfill due to issues with achieving compaction, a frost taper of 10H:1V can be implemented to help mitigate the potential for differential settlement and frost heave.

4.8 Pavement Design

The proposed development will have a network of roads as shown on the concept plan in Figure 2B.

4.8.1 Subgrade Preparation

For purposes of this report, the road grade is assumed to be at or just above the existing grade. Based on this the subgrade for the road is assumed to comprise engineered fill or the near surface soil noted in the boreholes, which range from low to high frost susceptibility.

The subgrade must be inspected and approved by the geotechnical engineer at the time of construction. If the subgrade does not comprise engineered fill, the exposed pavement subgrade should be compacted to a minimum 95% SPmdd. If any soft or weak subgrade areas are identified, or if there are areas containing excessive amounts of moisture or deleterious/organic material, they must be locally sub-excavated and backfilled with approved clean earth fill or imported granular material and compacted to a minimum of 95% SPmdd.



The long-term performance of the pavement structure is highly dependent upon the subgrade support conditions. Stringent construction control procedures must be maintained to ensure that uniform subgrade moisture and density conditions are achieved as much as possible when fill is placed, and the natural subgrade is not disturbed or weakened after it is exposed.

4.8.2 Drainage

Control of surface water is an important factor in achieving a good pavement life. The need for adequate subgrade drainage cannot be over-emphasized. The subgrade must be free of depressions and sloped (at a minimum grade of 2 percent) to provide effective drainage toward subgrade drains. Grading adjacent to pavement areas should be designed to ensure that water is not allowed to pond adjacent to the outside edges of the pavement.

Continuous pavement subdrains should be provided along both sides of the roadways and around the perimeter of parking areas and drained into respective catchbasins to facilitate drainage of the subgrade and the granular materials. The subdrain invert should be maintained at least 0.3 m below subgrade level. To minimize the problems of differential movement between the pavement and catchbasins/manholes due to frost action, the backfill around the structures should consist of free-draining OPSS Granular B. Typical pavement drainage details are provided in Appendix C.

4.8.3 Pavement Structure

The two different types of pavements for this project are defined below:

- <u>Light duty</u>: Includes parking lots which will not see frequent heavy traffic loads such
 as buses, delivery or fire trucks, etc., and will mostly service small vehicles such as
 cars or pickup trucks. In this case this design should be used for the parking lot used
 by the cars
- <u>Heavy Duty</u>: Includes access and driveways which are designated fire truck routes, or will see frequent heavy traffic loads such as school buses, delivery or garbage trucks, etc. In this case this design should be used for the driveway used by trucks and loading aprons.

The industry pavement design methods are based on a design life of 15 to 20 years for typical weather conditions depending on actual traffic volumes. The following pavement thickness designs are provided on the above noted considerations and conservatively based on the highly frost susceptible native soil. When the subgrade is confirmed, the designs can be finalized.

Pavement Layer	Compaction	Minimum Component Thickness	
·	Requirements	Light-Duty	Heavy-Duty
Surface Course Asphaltic Concrete: HL3 (OPSS 1150) with PG 58-28 Asphalt Cement (OPSS.MUNI 1101)	OPSS 310	40 mm	40 mm
Binder Course Asphaltic Concrete: HL8 (OPSS 1150) with PG 58-28 Asphalt Cement (OPSS.MUNI 1101)	OPSS 310	50 mm	80 mm
Base Course: Granular A (OPSS.MUNI 1010)	100% Standard Proctor Maximum Dry Density (ASTM-D698)	150 mm	150 mm
Subbase Course: Granular B Type I or II (OPSS.MUNI 1010)	100% Standard Proctor Maximum Dry Density (ASTM- D698)	450 mm	600 mm

The granular materials should be placed in lifts 200 mm thick or less and be compacted to a minimum of 100% SPmdd for both granular base and subbase. Asphalt materials should be rolled and compacted as per OPSS 310. The granular and asphalt pavement materials and their placement should conform to OPSS 310, 501, 1010 and 1150.

If the pavement construction occurs in wet, winter or inclement weather, it may be necessary to provide additional subgrade support for heavy construction traffic by increasing the thickness of the granular subbase, base or both. Further, traffic areas for construction equipment may experience unstable subgrade conditions. These areas may be stabilized utilizing additional thickness of granular materials or geogrid materials.

It should be noted that in addition to adherence of the above pavement design recommendations, a close control on the pavement construction process will also be required in order to obtain the desired pavement life. Therefore, it is recommended that regular inspection and testing should be conducted during the pavement construction to confirm material quality, thickness, and to ensure adequate compaction.

Frost tapers of 10H:1V should be implemented between areas of differing pavement thickness and tie-in areas to existing pavement.

Smooth transitions are required in all areas where the new pavement meets the existing asphalt surface (existing roads). Asphalt joints shall follow OPSS.MUNI 310. Longitudinal asphalt joints should be milled into the existing asphalt a minimum of 0.5 m for each lift. Transvers joint shall be milled into the existing asphalt a minimum 0.5 m for each lift. Successive joints should be staggered.

4.9 Stormwater Management Pond

A large SWM pond is currently proposed along the west edge of the development. The details of the pond have not yet been fully established and are in the design phase.

Boreholes 3 and 4 were drilled in the area of the proposed SWM pond. Below the surficial topsoil and local fill, a sand and silt unit was revealed to 1.5 to 2.3 m depth (Elev. 250.3 to 253.0). A silty clay unit was below the silt and sand unit with variable thickness (0.7 to 3.1 m) extending to 3.0 to 4.6 m depth (Elev. 247.2 to 253.3). The silty clay was underlain by the major till deposit, extending to the 6.6 m depth of exploration in Borehole 4 (Elev. 245.2) and to 6.1 m depth (Elev. 2492.) in Borehole 3. A basal sand layer was below the till in Borehole 3 to the 6.6 m depth of the borehole (Elev. 248.8).

4.9.1 General Construction Considerations

Excavation and temporary ground water control construction considerations are provided with Section 5.1 of this report and apply to the construction of the SWM pond.

The steepest recommended interior pond slope inclination is 5H:1V. The steepest recommended exterior berm slope inclination is 3H:1V. The pond design should follow the design guidelines of the City of Barrie.

It is recommended that any piping or trenching in the area of the pond should be provided with seepage cut-off collars (clay plugs, concrete plugs, or other barriers) to protect against water seepage through the pipe bedding and backfill.

Pond berms above grade will have to be constructed as engineered fill, constructed as described earlier in the report.

4.9.2 Pond Slope Surface Treatment

The final slope surface and all bare or exposed areas (where applicable) should be provided with suitable vegetation cover or erosion protection. The sloped surface should be provided with a layer of topsoil (minimum 100 mm thick) and should be hydro-seeded with a grass mixture and mulch. If seeded, during the first 2 to 3 years, the surface cover of topsoil and seeding may require periodic maintenance until the vegetation becomes well established. It is recommended that erosion netting/erosion control blankets be staked on the slope surface for erosion protection (including the inside slope above the water level).

4.9.3 Liner Considerations

Depending on the type of SWM pond that is planned, a liner may be required if a permanent pool is proposed. The liner should be placed along the entire pond bottom and extend a minimum of 1.0 m above the permanent pool elevation. The liner may consist of a natural soil



material (such as clay), a synthetic membrane liner (such as a High-Density Polyethylene, Geosynthetic Clay Liner, or PVC), a concrete liner, or a combination thereof. Details can be provided when the design has progressed.

The liner system must be designed to withstand uplift pressure due to hydrostatic head at the base of the liner for the worse-case condition when the pond is emptied for cleaning and maintenance activities. Uplift pressure can be assessed and reviewed when design details are established. A gravel/rip rap protection layer should also be considered for the liner when the pond is cleaned out in the future.

4.10 Infiltration Considerations

The predominant soil type(s) encountered on-site are summarized below with the interpreted unfactored infiltration rates:

Soil Type	Unfactored Infiltration Rate (mm/hr)
Sand/ Gravelly Sand	150 to 300
Silty Sand/Sand and Silt/Silt and Sand	50 to 75
Till	30
Silty Clay/Clayey Silt	Less than 10

Typical design of infiltration facilities has the base of the feature a minimum of 1 above the groundwater table. The infiltration rate provided below is not applicable below the groundwater table. As such, infiltration may not be practical/possible at some locations.

Appendix C of "Low Impact Development Stormwater Management and Planning Design Guide" (Version 1.0, 2010, by CVC and TRCA) suggests safety factors to be applied to infiltration rates. The safety factor applicable to the site is expected to be 2.5 but must be confirmed once the final location and elevation of LID measures are known.

Once LID plans are available, GEI recommends conducting Guelph Permeameter testing in the proposed footprints and infiltration elevations for the LID measures to determine the insitu infiltration rates of the soil.

5. Constructability Considerations

5.1 Excavations

At this time, excavations for the project site are anticipated to be about 3.0 to 4.0 m below existing grade to account for SWM ponds, buildings and servicing. Below the surficial topsoil and fill, excavations are anticipated to encounter the upper cohesionless units, clayey silt, silty clay, sand and silt/silt and sand, the glacial till and lower gravelly sand/sand. Harder digging can be expected in the dense to very dense soils. Cobbles and boulders can be expected in the glacial till.

Excavations must be carried out in accordance with the Occupational Health and Safety Act, Ontario Regulation 213/91 (as amended), Construction Projects, Part III - Excavations, Section 222 through 242. Where workers must enter a trench or excavation the soil must be suitably sloped and/or braced in accordance with the OHSA. These regulations designate four (4) broad classifications of soils to stipulate appropriate measures for excavation safety. If more than one soil type is encountered in an excavation, the most conservative soil type must be followed for sloping the sidewalls of the excavation. Excavations for the site should be completed considering a Type 3 soil geometry, 1H:1V from the base of the excavation, assuming that the soils are dewatered prior to excavation.

Excavation sidewalls will need to be continuously reviewed for evidence of instability and ground water seepage, particularly following periods of heavy rain or thawing. When required, remedial action must be taken to ensure the continued stability of excavation slopes and the safety of the workers.

Minimum support system requirements for steeper excavations are stipulated in Sections 235 through 238 and 241 of the OHSA and include provisions for timbering, shoring and moveable trench boxes. To reduce the potential for instability of the trench excavations, materials excavated from the service trenches and/or other fill materials or heavy equipment should not be placed near the crest of the trench excavations.

It is important to note that soil encountered in the construction excavations may vary significantly across the site. Our preliminary soil classifications are based solely on the materials encountered in the boreholes advanced on site. The contractor should verify that similar conditions exist throughout the proposed area of excavation. If different subsurface conditions are encountered at the time of construction, we recommend that GEI be contacted immediately to evaluate the conditions encountered.

5.2 Temporary Construction Groundwater Control

As noted above, excavation is envisioned to extend to about 3.0 to 4.0 m depth below existing grades for the project.

The stabilized groundwater levels in the monitoring wells are typically within about 2 m of the ground surface corresponding to Elev. 252.8 to 258.7. This is believed to reflect a combination of perched water in the upper soil units, wet seams or wet cohesionless layer in the till deposit and groundwater under sub-artesian pressure in the lower sand unit below the till.

The exact scenario where certain groundwater control techniques will work are directly correlated to how coarse/fine the native soils are in an excavation, and both the lateral and vertical extent of the wet cohesionless deposits encountered as noted above. If the groundwater table is not controlled during construction, the base of the excavations will be unstable, leading to difficulties in excavating and placement of pipes, footings or engineered fill, and providing safety for the workers.

Conventional sump pumping should suffice to control groundwater seepage for excavations that extend about 1.0 to 2.0 m below existing grade. Locally in sandier zones several sumps or keg wells may be required.

Deeper excavation will require pumping from multiple keg wells or dewatering, including depressurization of the lower sub-artesian pressurized sand and gravelly sand deposits.

It is recommended to carry out the work during the dry time of the year when the ground water table is lowest, to mitigate groundwater control measures. Also reducing the size of the excavation that is open at any one time will aid in reducing groundwater control requirements.

Based on the above, a Permit-to-Take-Water (PTTW) may be required depending on the design. Registry on the Environmental Activity and Sector Registry (EASR) system is considered to be required as a minimum.

A hydrogeological study is recommended for the site when the design details have been established to assess water taking analysis, regulatory requirements, impact assessments and monitoring plans, etc.

5.3 Compaction Specifications

SPmdd is the specification to indicate the degree to which soil or aggregate is compacted. To achieve the specified SPmdd as indicated in this report, all soils or aggregates must be placed in lift thicknesses no greater than 200 mm. If this is not the case, only the upper portion of the lift will be adequately compacted, and the lower portion of the lift has a high probability of not meeting compaction specifications. In addition, industry standard equipment used to determine



the degree of compaction consists of nuclear densometers. These devices have an inherent limitation in that they cannot test beyond 300 mm in depth, and so the degree of compaction beyond this depth cannot be quantitatively determined.

Along with lift thickness, ensuring that the soil or aggregate is within 2% of its optimum moisture content ensures that the specified compaction can be reached. If the soil or aggregate is too dry/wet, it is either very difficult or impossible to reach the specified compaction. This is especially true for when higher compaction specifications such as 98% and 100% SPmdd are required.

Based on our review of the soil types encountered in the boreholes with associated moisture contents, the soils at this site above the groundwater table are near optimum and the soil below the ground water table is wet of optimum.

Moisture can be increased by adding water and mixing the soil prior to re-use, blending the soil with wetter material, or by importing soil to the site that is at optimum and can be readily compacted.

Moisture can be reduced by tilling or spreading out the soil to dry or blending it with drier material. In-situ moisture contents can change based on the season and local groundwater levels and can also change for stockpiled material due to precipitation. Zones of the fine-grained soil beneath the site have very high moisture contents and moisture conditioning may be difficult to accomplish.

Excavated clayey soil from the site should not be re-used as engineered fill or common backfill because these soils have moisture contents well above optimum. Reducing moisture in the cohesive soil is likely not practical and the compaction specifications will not be achieved.

In addition to the above compaction specifications, in any areas where compacted fill will be placed over the exposed native soil subgrade, any loose, soft, wet, organic or unstable areas should be sub-excavated, and backfilled with clean earth fill or Granular 'B' (OPSS.MUNI 1010) compacted to a minimum of 95% SPmdd. This recommendation applies to site servicing and pavement subgrades. Where structures/buildings require upfilling beneath the structure the fill should be compacted to 100% SPmdd.

5.4 Quality Verification Services

On-site quality verification services are an integral part of the geotechnical design function, and for foundations, engineered fill and retaining walls, are required under the Ontario Building Code. Quality verification services are used to confirm that construction is being conducted in general conformance with the requirements as outlined in the drawings, reports and specifications prepared for the proposed development.



GEI Consultants can provide all the on-site quality verification services outlined below:

- The subgrade for shallow foundations for buildings must be field reviewed by the geotechnical engineer as required by the municipal regulating authority.
- Installation of retaining structures over 1.0 m high and related backfilling operations must be field reviewed on a continuous basis by the geotechnical engineer as required in the OBC.
- Full-time monitoring, testing and inspection of engineered fill placement is required by the geotechnical engineer per the OBC.
- Part-time monitoring of the subgrade support capabilities, material quality, lift thickness, moisture content, degree of compaction, etc. is recommended for the following areas to ensure the recommendations within this report are followed and they perform adequately in the long-term;
 - Slab-on-grades;
 - Pavement structure (granular and asphalt); and
 - Bedding/backfilling of site servicing.
- Testing of the concrete (compressive strength, slump, air content, etc.) and testing of the asphalt (asphalt content and gradation) are recommended to ensure that the quality of the materials being brought to site meet the requirements of the project.

5.5 Site Work

The soils found at this site may become weakened when subjected to traffic, particularly when wet. If there is site work carried out during periods of wet weather, then it can be expected that the subgrade will be disturbed unless an adequate granular working surface is provided to protect the integrity of the subgrade soils from construction traffic. Subgrade preparation works cannot be adequately accomplished during wet weather and the project must be scheduled accordingly. The disturbance caused by the traffic can result in the removal of disturbed soil and use of granular fill material for site restoration or underfloor fill that is not intrinsic to the project requirements.

The most severe loading conditions on the subgrade may occur during construction. Consequently, special provisions such as end dumping and forward spreading of earth and aggregate fills, restricted construction lanes, and half-loads during paving and other work may be required, especially if construction is carried out during unfavourable weather.

If construction proceeds during freezing weather conditions, adequate temporary frost protection for the founding subgrade and concrete must be provided. The soil at this site is susceptible to frost damage. Consideration must be given to frost effects, such as heave or softening, on exposed soil surfaces in the context of this particular project development.

6. Limitations and Conclusions

6.1 Limitations

The recommendations and comments provided are necessarily on-going as new information of underground conditions becomes available. More specific information with respect to the conditions between samples, or the lateral and vertical extent of materials may become apparent during excavation operations. The interpretation of the borehole information must, therefore, be validated during excavation operations. Consequently, conditions not observed during this investigation may become apparent. Should this occur, GEI should be contacted to assess the situation and additional testing and reporting may be required.

GEI should be retained for a general review of the final design drawings and specifications to verify that this report has been properly interpreted and implemented. If not accorded the privilege of making this review, GEI will assume no responsibility for interpretation of the recommendations in the report.

The comments given in this report are intended only for the guidance of the design engineers. The number of boreholes required to determine the localized underground conditions between boreholes affecting construction costs, techniques, sequencing, equipment, scheduling, etc. could be greater than has been carried out for design purposes. Contractors bidding on or undertaking the works should, in this light, decide on their own investigations, as well as their own interpretations of the factual borehole results, so that they may draw their own conclusions as to how the subsurface conditions may affect them.

This report was authorized by, and prepared by GEI for, the account of Hansen Group Inc. (as provided in the signed Standard Professional Services Agreement). Any use which a third party makes of this report, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. GEI accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on this project.

6.2 Conclusion

It is recognized that municipal/regional governing bodies, in their capacity as the planning and building authority under Provincial statues, will make use of and rely upon this report, cognizant of the limitations thereof, both as are expressed and implied.

We trust this report is complete within our terms of reference, and the information presented is sufficient for your present purposes. If you have any questions, or when we may be of further assistance, please do not hesitate to contact our office.

Yours Truly,

GEI Consultants





Geoffrey R. White, P.Eng. Geotechnical Practice Lead


Figures

Site Location Plan
Borehole Location Plans









Appendix A

Borehole Logs



RECORD OF BOREHOLE No. 1

Hansen Group Inc.

Project Number: 2304675




Project Name: Hewitt's South Residential Subdivision

Project Location: Lockhart Road, Barrie, ON Logged By: ВН __ Northing: __ 4910627 Date Started: Nov 2/23 **Drilling Location:** See Borehole Location Plan Reviewed By: GW Easting: 610864 Date Completed: Nov 2/23

Local Benchmark:

Project Client:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: Dry

Cave depth after auger removal: Open

Groundwater depth observed on: Nov 29/23 at depth of: 0.5 m. Groundwater Elevation: 255.8 m

RECORD OF BOREHOLE No. 2

Project Number: 2304675



Project Client: Hansen Group Inc. Drilling Method: Solid Stem Augers Project Name: Hewitt's South Residential Subdivision _____ Drilling Machine: Track Mount

Logged By:

Reviewed By:

ВН

__ Northing: __

GW Easting:


Date Started: Nov 2/23

Project Location: Lockhart Road, Barrie, ON **Drilling Location:** See Borehole Location Plan

610918 Date Completed: Nov 2/23

4910625

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: 2.3 m.

Cave depth after auger removal: 3.3 m.

Groundwater depth observed on: Nov 29/23 at depth of: 0.4 m. Groundwater Elevation: 255.7 m

RECORD OF BOREHOLE No. 3

Project Number: 2304675




Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: ВН __ Northing: __ 4910732 Date Started: Nov 2/23 GW ___ Easting: __ **Drilling Location:** See Borehole Location Plan Reviewed By: 611039 Date Completed: Nov 2/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

¥ Groundwater depth encountered on completion of drilling: 3.3 m. \mathbf{Z}

Groundwater depth observed on:

Cave depth after auger removal: Open

Groundwater Elevation:

Project Number: 2304675



Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision

Drilling Method: Solid Stem Augers Drilling Machine: Track Mount
Logged By: BH Northing: 4910870 Date Started:

GW Easting:


Project Location: Lockhart Road, Barrie, ON

Drilling Location: See Borehole Location Plan

 4910870
 Date Started:
 Nov 6/23

 610971
 Date Completed:
 Nov 6/23

Local Benchmark:




Reviewed By:

GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com Groundwater depth encountered on completion of drilling: Dry

Cave depth after auger removal: Open

Project Number: 2304675

Hewitt's South Residential Subdivision



Project Client: Hansen Group Inc.

> Drilling Method: Solid Stem Augers _____ Drilling Machine: Track Mount __ Northing: __


ВН

GW Easting:

Project Location: Lockhart Road, Barrie, ON **Drilling Location:** See Borehole Location Plan 4911048 Date Started: Nov 8/23 611407 Date Completed: Nov 8/23

Local Benchmark:

Project Name:



Logged By:

Reviewed By:

GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: Dry Cave depth after auger removal: Open

Groundwater depth observed on: Nov 29/23 at depth of: 1.8 m.

Groundwater Elevation: 255.8 m

Project Number: 2304675




Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision

Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: ВН __ Northing: ___ 4911054 Date Started: Nov 8/23 GW ___ Easting: **Drilling Location:** See Borehole Location Plan Reviewed By: 611351 Date Completed: Nov 8/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: 5.4 m.

Cave depth after auger removal: Open

Groundwater depth observed on: Nov 29/23 at depth of: 1.2 m. Groundwater Elevation: 254.0 m

Project Number: 2304675



Project Client: Hansen Group Inc.


Project Name: Hewitt's South Residential Subdivision

Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: BH Northing: 4911010 Date Started: Nov 8/23

Drilling Location: See Borehole Location Plan Reviewed By: GW Easting: 611327 Date Completed: Nov 8/23

Local Benchmark:



GEI CONSULTANTS
647 Welham Road, Unit 14
Barrie, Ontario L4N 0B7
T: (705) 719-7994
www.geiconsultants.com

 \mathbf{Z}

Groundwater depth encountered on completion of drilling: 3.0 m.

Cave depth after auger removal: Open

Groundwater depth observed on: Groundw

Project Number: 2304675




Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision

Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: ВН __ Northing: __ 4910896 Date Started: Nov 8/23 **Drilling Location:** See Borehole Location Plan Reviewed By: GW Easting: 611271 Date Completed: Nov 8/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: 3.0 m.

Cave depth after auger removal: 4.2 m.

Groundwater depth observed on:

Project Number: 2304675




Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: BH Northing: 4910926 Date Started: Nov 8/23

Drilling Location: See Borehole Location Plan Reviewed By: GW Easting: 611360 Date Completed: Nov 8/23

Local Benchmark:



GEI CONSULTANTS
647 Welham Road, Unit 14
Barrie, Ontario L4N 0B7
T: (705) 719-7994
www.geiconsultants.com

 \mathbf{Z}

Groundwater depth encountered on completion of drilling: 1.9 m.

Cave depth after auger removal: 0.1 m.

Groundwater depth observed on: Nov 29/23 at depth of: 1.3 m.

Groundwater Elevation: 256.7 m

Project Number: 2304675




Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: ВН Northing: 4910953 Date Started: Nov 8/23 GW ___ Easting: __ **Drilling Location:** See Borehole Location Plan Reviewed By: 611458 Date Completed: Nov 8/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

¥ Groundwater depth encountered on completion of drilling: 1.8 m. \mathbf{Z}

Groundwater depth observed on:

Cave depth after auger removal: 4.0 m.

Project Number: 2304675



Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount


ВН

Project Location: Lockhart Road, Barrie, ON **Drilling Location:** See Borehole Location Plan

__ Northing: __ 4910864 Nov 7/23 GW Easting: 611516 Date Completed: Nov 7/23

Date Started:

Local Benchmark:



Logged By:

Reviewed By:

GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: Dry

Cave depth after auger removal: Open

Groundwater depth observed on: Nov 29/23 at depth of: 3.9 m.

Groundwater Elevation: 258.7 m

Project Number: 2304675



Nov 6/23

Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Logged By:

Reviewed By:

ВН

__ Northing: __


GW ___ Easting:

Project Location: Lockhart Road, Barrie, ON **Drilling Location:** See Borehole Location Plan

Date Started: 611070 Date Completed: Nov 6/23

4910835

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: 2.4 m.

Groundwater depth observed on: Nov 29/23 at depth of: Blocked

Cave depth after auger removal: Open

Hansen Group Inc.

Project Number: 2304675



611177

Easting:

Project Name: Hewitt's South Residential Subdivision Project Location: Lockhart Road, Barrie, ON Logged By: ВН __ Northing: __

Reviewed By:

GW


4910916 Date Started: Nov 6/23

Date Completed: Nov 6/23

Drilling Location: See Borehole Location Plan

Local Benchmark:

Project Client:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: Dry

Groundwater depth observed on: Nov 29/23 at depth of: Blocked

Cave depth after auger removal: Open

Project Number: 2304675

Hewitt's South Residential Subdivision



Project Client: Hansen Group Inc.

> Drilling Method: Solid Stem Augers ____ Drilling Machine: Track Mount


> > Easting:

BH

GW

Project Location: Lockhart Road, Barrie, ON **Drilling Location:** See Borehole Location Plan Northing: 4910860 Date Started: Nov 6/23 611167 Date Completed: Nov 6/23

Project Name:



Logged By:

Reviewed By:

GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: 3.5 m.

Cave depth after auger removal: 4.5 m.

Groundwater depth observed on: Nov 29/23 at depth of: 1.2 m.

Groundwater Elevation: 252.8 m

Hansen Group Inc.

Project Number: 2304675

See Borehole Location Plan



Project Name: Hewitt's South Residential Subdivision Project Location: Lockhart Road, Barrie, ON Logged By: ВН __ Northing: __

Date Started:


Nov 3/23

GW ___ Easting: __ Reviewed By: 611165 Date Completed: Nov 3/23

4910802

Drilling Location: Local Benchmark:

Project Client:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: 5.1 m.

Cave depth after auger removal: 5.8 m.

Groundwater depth observed on: Nov 29/23 at depth of: 2.1 m. Groundwater Elevation: 253.5 m

Hansen Group Inc.


Project Number: 2304675 Project Client:

Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Name: Hewitt's South Residential Subdivision Project Location: Lockhart Road, Barrie, ON Logged By: ВН __ Northing: __ 4910709 Date Started:

Nov 2/23 GW ___ Easting: __ **Drilling Location:** See Borehole Location Plan Reviewed By: 611111 Date Completed: Nov 2/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: Dry

Cave depth after auger removal: Open

Groundwater depth observed on: Nov 29/23 at depth of: 2.1 m. Groundwater Elevation: 253.9 m

Hansen Group Inc.

Project Number: 2304675



Nov 3/23

Project Client: Project Name:

Hewitt's South Residential Subdivision

Drilling Method: Solid Stem Augers _____ Drilling Machine: Track Mount

GW Easting:

__ Northing: __

МН

Logged By:


Reviewed By:

Date Started:

Project Location: **Drilling Location:**

Lockhart Road, Barrie, ON See Borehole Location Plan 4910737 611191 Date Completed: Nov 3/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: 5.8 m.

Cave depth after auger removal: Open

Groundwater depth observed on: Nov 29/23 at depth of: 3.0 m. Groundwater Elevation: 254.1 m

Project Number: 2304675



Date Completed: Nov 7/23

Project Client: Hansen Group Inc.

Lockhart Road, Barrie, ON

See Borehole Location Plan

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Reviewed By:


Logged By: BH Northing: 4910826 Date Started: Nov 7/23

611295

GW ___ Easting: __

Drilling Location:
Local Benchmark:

Project Location:



GEI CONSULTANTS
647 Welham Road, Unit 14
Barrie, Ontario L4N 0B7
T: (705) 719-7994
www.geiconsultants.com

 \mathbf{Z}

Groundwater depth encountered on completion of drilling: 3.0 m.

Cave depth after auger removal: 4.0 m.

Groundwater depth observed on: Nov 29/23 at depth of: 2.0 m. Groundwater Elevation: 257.6 m

Project Number: 2304675




Project Client: Hansen Group Inc.

Drilling Method: Solid Stem Augers Project Name: Hewitt's South Residential Subdivision _____ Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: ВН __ Northing: __ 491860 Date Started: Nov 8/23 **Drilling Location:** See Borehole Location Plan Reviewed By: **GW** Easting: 611326 Date Completed: Nov 8/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: 1.2 m.

Cave depth after auger removal: 4.4 m.

Groundwater depth observed on: Nov 29/23 at depth of: 1.7 m. Groundwater Elevation: 257.6 m

Project Number: 2304675



Project Client: Hansen Group Inc.

Lockhart Road, Barrie, ON

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Logged By:

ВН

Date Started: Nov 7/23


Drilling Location: See Borehole Location Plan

Project Location:

Reviewed By: _____ Easting: _____ 611455 ____ Date Completed: _____ Nov 7/23

4910882

__ Northing: __



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

Groundwater depth encountered on completion of drilling: 3.0 m.

Cave depth after auger removal: 4.5 m.

Groundwater depth observed on: Nov 29/23 at depth of: 3.4 m. Groundwater Elevation: 258.4 m

Project Number: 2304675



Project Client: Hansen Group Inc.


Project Name: Hewitt's South Residential Subdivision

Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: BH Northing: 4910795 Date Started: Nov 7/23

Drilling Location: See Borehole Location Plan Reviewed By: GW Easting: 611353 Date Completed: Nov 7/23

Local Benchmark:



GEI CONSULTANTS
647 Welham Road, Unit 14
Barrie, Ontario L4N 0B7
T: (705) 719-7994
www.geiconsultants.com

Groundwater depth encountered on completion of drilling: 4.8 m.

Cave depth after auger removal: 3.0 m.

Groundwater depth observed on: Nov 29/23 at depth of: 5.4 m.

Groundwater Elevation: 258.2 m

Project Number: 2304675




Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision

Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: ВН __ Northing: __ 4910862 Date Started: Nov 6/23 GW ___ Easting: **Drilling Location:** See Borehole Location Plan Reviewed By: 611114 Date Completed: Nov 6/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: Dry Cave depth after auger removal: Open

Groundwater depth observed on:

Project Number: 2304675




Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: BH Northing: 4910770 Date Started: Nov 3/23

Drilling Location: See Borehole Location Plan Reviewed By: GW Easting: 611116 Date Completed: Nov 3/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

Groundwater depth encountered on completion of drilling: 2.7 m.

Cave depth after auger removal: 4.8 m.

Groundwater depth observed on: Groundwater Elevation:

Project Number: 2304675




Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: ВН __ Northing: __ 4910712 Date Started: Nov 2/23 GW ___ Easting: __ **Drilling Location:** See Borehole Location Plan Reviewed By: 611170 Date Completed: Nov 2/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

¥ Groundwater depth encountered on completion of drilling: 5.8 m. Cave depth after auger removal: Open \mathbf{Z} Groundwater depth observed on:

Project Number: 2304675



Nov 3/23

Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision

Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

GW ___ Easting:

Northing:

ВН

Logged By:

Reviewed By:


Project Location: Lockhart Road, Barrie, ON **Drilling Location:** See Borehole Location Plan

611220 Date Completed: Nov 3/23

Date Started:

4910834

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

¥ Groundwater depth encountered on completion of drilling: 1.8 m.

Groundwater depth observed on:

Cave depth after auger removal: 4.1 m.

Project Number: 2304675



Date Started:

Nov 3/23

Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount Northing:


ВН

Project Location: Lockhart Road, Barrie, ON **Drilling Location:** See Borehole Location Plan

GW ___ Easting: __ 611244 Date Completed: Nov 3/23

4910747

Local Benchmark:



Logged By:

Reviewed By:

GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

¥ Groundwater depth encountered on completion of drilling: 3.3 m.

Cave depth after auger removal: 3.6 m.

 \mathbf{Z} Groundwater depth observed on:

Project Number: 2304675



Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers

Logged By:

Reviewed By:

ВН

__ Northing: __

GW Easting:

Drilling Machine: Track Mount


Project Location: Lockhart Road, Barrie, ON

Drilling Location: See Borehole Location Plan

 4910874
 Date Started:
 Nov 7/23

 611381
 Date Completed:
 Nov 7/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

 \mathbf{Z}

 $\stackrel{ extstyle op}{=}$ Groundwater depth encountered on completion of drilling: 3.3 m. $\stackrel{ extstyle op}{=}$

Cave depth after auger removal: 3.3 m.

Groundwater depth observed on:

Project Number: 2304675




Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Project Location: Lockhart Road, Barrie, ON Logged By: ВН ___ Northing: ___ 4910807 Date Started: Nov 7/23 GW ___ Easting: __ **Drilling Location:** See Borehole Location Plan Reviewed By: 611418 Date Completed: Nov 7/23

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

¥ Groundwater depth encountered on completion of drilling: 3.8 m. \mathbf{L}

Groundwater depth observed on:

Cave depth after auger removal: 4.1 m.

Project Number: 2304675



Project Client: Hansen Group Inc.

Project Name: Hewitt's South Residential Subdivision Drilling Method: Solid Stem Augers Drilling Machine: Track Mount

Logged By:

ВН


4910832 Date Started: Nov 7/23

Project Location: Lockhart Road, Barrie, ON **Drilling Location:** See Borehole Location Plan

GW ___ Easting: __ Reviewed By: 611537 Date Completed: Nov 7/23

__ Northing: __

Local Benchmark:



GEI CONSULTANTS 647 Welham Road, Unit 14 Barrie, Ontario L4N 0B7 T: (705) 719-7994 www.geiconsultants.com

¥ Groundwater depth encountered on completion of drilling: 5.1 m.


Cave depth after auger removal: 5.3 m.


 \mathbf{Z} Groundwater depth observed on:


Appendix B


Geotechnical Laboratory Testing













Atterberg Limits Report

Project Name: Pratt Hansen Phase 3


Project No.: 2304675 Client: Figure No.: B5

Date Tested: December 12, 2023

Date Sampled: December 1, 2023

240 Vanipion 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2 2								
SAMPLE INFORMATION								
SAMPLE ID	BH13, SS3	LIQUID LIMIT (LL):	48	PLASTIC LIMIT (PL)	23.8	PLASTIC INDEX (PI)	24.2	Х
SAMPLE ID	BH4, SS5	LIQUID LIMIT (LL):	50.3	PLASTIC LIMIT (PL)	20.4	PLASTIC INDEX (PI)	29.9	A
SAMPLE ID	BH5, SS3	LIQUID LIMIT	45.1	PLASTIC I IMIT (PL)	21.5	PLASTIC INDEX (PI)	23.6	+

Plasticity Chart




DISTRIBUTION:	Prepared By: X.Guo	Checked By:

Appendix C

Previous Borehole Information





LIST OF ABBREVIATIONS



PENETRATION RESISTANCE

Standard Penetration Resistance N: - The number of blows required to advance a standard split spoon sampler 0.3 m into the subsoil. Driven by means of a 63.5 kg hammer falling freely a distance of 0.76 m.

Dynamic Penetration Resistance: - The number of blows required to advance a 51 mm, 60 degree cone, fitted to the end of drill rods, 0.3 m into the subsoil. The driving energy being 475 J per blow.

DESCRIPTION OF SOIL

The consistency of cohesive soils and the relative density or denseness of cohesionless soils are described in the following terms:

CONSISTE	NCY N (blows/0.3 m)	<u>c (kPa)</u>	<u>DENSENESS</u>	N (blows/0.3 m)
Very Soft	0 - 2	0 - 12	Very Loose	0 - 4
Soft	2 - 4	12 - 25	Loose	4 - 10
Firm	4 - 8	25 - 50	Compact	10 - 30
Stiff	8 - 15	50 - 100	Dense	30 - 50
Very Stiff	15 - 30	100 - 200	Very Dense	> 50
Hard	> 30	> 200		
WTPL	Wetter Than Plastic Limit			
APL	About Plastic Limit			
DTPL	Drier Than Plastic Limit			

TYPE OF SAMPLE

SS	Split Spoon	TW	Thinwall Open	
WS	Washed Sample	TP	Thinwall Piston	
SB	Scraper Bucket Sample	os	Oesterberg Sample	
AS	Auger Sample	FS	Foil Sample	
CS	Chunk Sample	RC	Rock Core	
ST	Slotted Tube Sample			
DIL Carrella Advance ed Lleider disable				

PH Sample Advanced Hydraulically
PM Sample Advanced Manually

SOIL TESTS

Qu	Unconfined Compression	LV	Laboratory Vane
Q	Undrained Triaxial	FV	Field Vane
Qcu	Consolidated Undrained Triaxial	С	Consolidation
Qd	Drained Triaxial		

PML-GEO-508A Rev. 2004-01



LOG OF BOREHOLE/MONITORING WELL NO. 101 1 of 1 17T 610974E 4910966N PROJECT Proposed Hewitt's Gate East Residential Development - Phase 3 PMI RFF 21BF052 LOCATION Barrie, Ontario BORING DATE December 13, 2022 **ENGINEER** FM **BORING METHOD** Continuous Flight Hollow Stem Augers TECHNICIAN FF SHEAR STRENGTH (kPa) SOIL PROFILE **SAMPLES** +FIELD VANE ΔTORVANE O Qu PLASTIC MOISTURE APOCKET PENETROMETER O QU PLASTIC MOISTURE LIMIT CONTENT SCAL **GROUND WATER** LIMIT ▲POCKET PENETROMETER **O** Q CONTENT **OBSERVATIONS** VALUES NUMBER W 100 150 200 **EVATION** AND REMARKS DESCRIPTION ELEV LNN DYNAMIC CONE PENETRATION X STANDARD PENETRATION TEST metres **GRAIN SIZE** WATER CONTENT (%) z DISTRIBUTION (%) GR SA SI CL 핍 10 20 30 SURFACE ELEVATION 251.50 20 40 60 40 kN/m 0.0 TOPSOIL: Black, sandy silt, trace gravel, Stick up casing 0.30 251.20 trace organics, moist SS 9 Concrete SAND: Loose to compact, brown, sand, some silt, trace gravel, moist to wet First water strike at 2 SS 1.0 10 0 0.7 mCLAY AND SILT: Firm to stiff, grey, clay and silt, some sand, trace gravel, APL 3¹ SS 10 2.0 4 SS 9 249 Bentonite seal 5 SS 7 0 4.0 TILL: Loose to very dense, grey, silty sand, some clay, trace to some gravel, cobbles and possible boulders, wet to moist 6 SS 6 5.0 246 6.0 SS 50 mm slotted pipe 7.0 Filter sand 8 SS 50/130 mm 8.0 243.4 BOREHOLE TERMINATED AT 8.1 m Upon completion of augering Water at 4.6 m No cave Water Level Readings: Depth Elev. Date 9.0 2022-01-04 FROZEN 252.3 2022-06-08 -0.8 252.3 10.0 11.0 12.0 13.0 14.0 15.0 NOTES 1. Sample submitted for chemical testing



LOG OF BOREHOLE/MONITORING WELL NO. 102 1 of 1 17T 611000E 4910907N PROJECT Proposed Hewitt's Gate East Residential Development - Phase 3 PMI RFF 21BF052 LOCATION Barrie, Ontario BORING DATE December 13, 2022 **ENGINEER** FM **BORING METHOD** Continuous Flight Hollow Stem Augers TECHNICIAN FF SHEAR STRENGTH (kPa) **SAMPLES** SOIL PROFILE +FIELD VANE ΔTORVANE O Qu PLASTIC MOISTURE LIMIT MOISTURE SCAL **GROUND WATER** LIMIT ▲POCKET PENETROMETER OQ CONTENT **OBSERVATIONS** VALUES NUMBER W 100 150 200 **EVATION** AND REMARKS DESCRIPTION ELEV HNN DYNAMIC CONE PENETRATION X STANDARD PENETRATION TEST metres **GRAIN SIZE** WATER CONTENT (%) z DISTRIBUTION (%) GR SA SI CL 핍 10 20 30 SURFACE ELEVATION 251.85 20 40 60 40 kN/m 0.0 TOPSOIL: Black, sandy silt, trace gravel, Stick up casing 0.30 251.55 trace organics, moist SS 9 0 Concrete SAND: Loose, brown, sand, trace silt, 0.70 moist 251.15 CLAY AND SILT: Stiff, grey, clay and silt, some sand, trace gravel, APL 2 SS 14 0 3¹ SS 13 0 12 40 48 250 2.0 Bentonite seal 4 SS 15 TILL: Compact to dense, grey, silty sand, 249.0 some clay, some gravel, cobbles and possible boulders, moist SS 5 16 248 4.0 6 SS 17 First water strike at 5.0 4.6 m 50 mm slotted pipe Filter sand 246 6.0 SS 245 7.0 244 becoming wet 8 SS 33 8.0 BOREHOLE TERMINATED AT 8.1 m Upon completion of augering Water at 7.5 m No cave Water Level Readings: Depth Elev. FROZEN 252.7 Date 9.0 2022-01-04 2022-06-08 -0.8 10.0 11.0 12.0 13.0 14.0 15.0 NOTES 1. Sample submitted for chemical testing



LOG OF BOREHOLE/MONITORING WELL NO. 103 1 of 1 17T 611406E 4911170N PROJECT Proposed Hewitt's Gate East Residential Development - Phase 3 PMI RFF 21BF052 LOCATION Barrie, Ontario BORING DATE December 14, 2022 **ENGINEER** FM **BORING METHOD** Continuous Flight Hollow Stem Augers TECHNICIAN FF SHEAR STRENGTH (kPa) **SAMPLES** SOIL PROFILE +FIELD VANE ΔTORVANE O Qu PLASTIC MOISTURE LIMIT MOISTURE SCAL **GROUND WATER** LIMIT ▲POCKET PENETROMETER OQ CONTENT **OBSERVATIONS** VALUES NUMBER W 100 150 200 **EVATION** AND REMARKS DESCRIPTION ELEV HNN DYNAMIC CONE PENETRATION X STANDARD PENETRATION TEST metres **GRAIN SIZE** WATER CONTENT (%) z DISTRIBUTION (%) GR SA SI CL 핍 10 20 30 SURFACE ELEVATION 256.35 20 40 60 40 kN/m 0.0 0.20 TOPSOIL: Black, sandy silt, trace gravel, Stick up casing 256.15 trace organics, moist 1 SS 5 Concrete 256 SAND: Loose, brown, sand, trace silt, 0.70 255.65 trace gravel, moist CLAY AND SILT: Stiff, brown, clay and 2 1.0 SS 9 0 silt, trace sand, trace gravel, APL TILL: Loose to dense, grey, silty sand, some clay, some gravel, cobbles and possible boulders, moist 3¹ SS 12 2.0 4 SS 8 Bentonite seal 3.0 5 SS 10 4.0 252 6 SS 17 5.0 6.0 SS 250 First water strike at 7.0 6.7 m 50 mm slotted pipe SAND: Compact, grey, sand, trace 249.3 249 Filter sand gravel, wet 8 SS 8.0 248.3 BOREHOLE TERMINATED AT 8.1 m Upon completion of augering Water at 2.4 m No cave Water Level Readings: Depth Date 9.0 2022-01-04 0.9 2022-06-08 10.0 11.0 12.0 13.0 14.0 15.0 NOTES 1. Sample submitted for chemical testing



LOG OF BOREHOLE/MONITORING WELL NO. 104 1 of 1 17T 611415E 4911123N PROJECT Proposed Hewitt's Gate East Residential Development - Phase 3 PMI RFF 21BF052 LOCATION Barrie, Ontario BORING DATE December 14, 2022 **ENGINEER** FM **BORING METHOD** Continuous Flight Hollow Stem Augers TECHNICIAN FF SHEAR STRENGTH (kPa) **SAMPLES** SOIL PROFILE +FIELD VANE ΔTORVANE O Qu PLASTIC MOISTURE APOCKET PENETROMETER O QU PLASTIC MOISTURE LIMIT CONTENT SCAL **GROUND WATER** LIMIT ▲POCKET PENETROMETER OQ CONTENT **OBSERVATIONS** VALUES NUMBER W 100 150 200 **EVATION** AND REMARKS DESCRIPTION ELEV LNN DYNAMIC CONE PENETRATION X STANDARD PENETRATION TEST GRAIN SIZE DISTRIBUTION (%) GR SA SI CL metres WATER CONTENT (%) z 핍 10 20 30 SURFACE ELEVATION 256.50 20 40 60 40 kN/m 0.0 TOPSOIL: Black, sandy silt, trace gravel, Stick up casing 0.30 256.20 trace organics, moist SS 8 SAND: Compact, brown, sand, trace silt, very moist 2 1.0 SS 17 0 Bentonite seal 255.1 TILL: Loose to compact, grey, sandy silt, some clay to clayey, some gravel, cobbles and possible boulders, moist to 3¹ SS 10 2.0 very moist 4 SS 10 3.0 5 SS 7 50 mm slotted pipe Filter sand becoming dense, silty sand, some clay, 252.5 First water strike trace to some gravel at 4.0 m 6 SS 19 15 39 34 12 5.0 251 6.0 SS 8 SS 35 0 8.0 248.4 BOREHOLE TERMINATED AT 8.1 m Upon completion of augering Water at 3.9 m No cave Water Level Readings: Depth Elev. Date 9.0 2022-01-04 255.4 255.7 2022-06-08 8.0 10.0 11.0 12.0 13.0 14.0 15.0 NOTES 1. Sample submitted for chemical testing



LOG OF BOREHOLE/MONITORING WELL NO. 105 1 of 1 17T 611249E 4910979N PROJECT Proposed Hewitt's Gate East Residential Development - Phase 3 PMI RFF 21BF052 LOCATION Barrie, Ontario BORING DATE December 13, 2022 **ENGINEER** FM **BORING METHOD** Continuous Flight Hollow Stem Augers TECHNICIAN FF SHEAR STRENGTH (kPa) SOIL PROFILE **SAMPLES** +FIELD VANE ΔTORVANE O Qu PLASTIC MOISTURE APOCKET PENETROMETER O QU PLASTIC MOISTURE LIMIT CONTENT SCAL **GROUND WATER** LIMIT ▲POCKET PENETROMETER OQ CONTENT **OBSERVATIONS** VALUES NUMBER W 100 **EVATION** AND REMARKS DESCRIPTION ELEV LNN DYNAMIC CONE PENETRATION X STANDARD PENETRATION TEST GRAIN SIZE DISTRIBUTION (%) GR SA SI CL metres WATER CONTENT (%) z 핍 10 20 20 30 40 SURFACE ELEVATION 254.80 40 60 kN/m 0.0 TOPSOIL: Black, silty sand, trace gravel, Stick up casing trace organics, moist SS 5 0 Concrete SAND: Compact, brown, sand, some silt, trace gravel, moist SS 2 1.0 10 TILL: Compact to dense, grey, silty sand, some clay, some gravel, cobbles and possible boulders, moist 253.4 3¹ SS 10 2.0 Bentonite seal 4 SS 13 3.0 SS 5 20 6 SS 28 250 5.0 50 mm slotted pipe Filter sand 249 6.0 SS 0 7 39 248.3 BOREHOLE TERMINATED AT 6.5 m Upon completion of augering Water at 6.0 m 7.0 No cave Water Level Readings: Date 2022-01-04 Depth 0.5 Elev. 254.3 2022-06-08 0.6 254.2 8.0 9.0 10.0 11.0 12.0 13.0 14.0 15.0 NOTES 1. Sample submitted for chemical testing



LOG OF BOREHOLE/MONITORING WELL NO. 106 1 of 1 17T 611104E 4910699N PROJECT Proposed Hewitt's Gate East Residential Development - Phase 3 PMI RFF 21BF052 LOCATION Barrie, Ontario BORING DATE December 13, 2022 **ENGINEER** FM **BORING METHOD** Continuous Flight Hollow Stem Augers TECHNICIAN FF SHEAR STRENGTH (kPa) SOIL PROFILE **SAMPLES** +FIELD VANE ΔTORVANE O Qu PLASTIC MOISTURE APOCKET PENETROMETER O QU PLASTIC MOISTURE LIMIT CONTENT SCAL **GROUND WATER** LIMIT ▲POCKET PENETROMETER OQ CONTENT STRAT PLOT **OBSERVATIONS** VALUES NUMBER W 100 150 200 **EVATION** AND REMARKS DESCRIPTION ELEV HNN DYNAMIC CONE PENETRATION X STANDARD PENETRATION TEST metres WATER CONTENT (%) **GRAIN SIZE** z DISTRIBUTION (%) GR SA SI CL 핍 10 20 30 SURFACE ELEVATION 256.20 20 40 60 40 kN/m 0.0 TOPSOIL: Black, silty sand, trace Stick up casing 256 organics, moist 1 SS 11 Concrete SILTY CLAY: Stiff, brown to grey, silty 0.70 clay, trace sand, moist TILL: Loose to compact, brown to grey, 2 SS 9 silty sand, some clay, trace gravel, moist 255 3¹ SS 9 45 34 12 2.0 4 SS 27 3.0 SS 5 25 Bentonite seal CLAY AND SILT: Stiff, grey, clay and silt, 252 some sand, APL First water strike at 6 SS 14 5.0 250.6 TILL: Compact to dense, grey, silty sand, some clay, some gravel, cobbles and 6.0 possible boulders, very moist to wet 250 SS 7.0 249 SS 8 8.0 248 50 mm slotted pipe 9.0 10.0 246.2 BOREHOLE TERMINATED AT 10.0 m Upon completion of augering Water at 4.6 m No cave Water Level Readings: Depth Elev. Date 11.0 2022-01-04 254.7 1.5 2022-06-08 1.6 254.6 12.0 13.0 14.0 15.0 NOTES 1. Sample submitted for chemical testing



LOG OF BOREHOLE/MONITORING WELL NO. 107 1 of 1 17T 611311E 4910770N PROJECT Proposed Hewitt's Gate East Residential Development - Phase 3 PMI RFF 21BF052 LOCATION Barrie, Ontario BORING DATE December 14, 2022 **ENGINEER** FM **BORING METHOD** Continuous Flight Hollow Stem Augers TECHNICIAN FF SHEAR STRENGTH (kPa) SOIL PROFILE **SAMPLES** +FIELD VANE ΔTORVANE O Qu PLASTIC MOISTURE APOCKET PENETROMETER O QU PLASTIC MOISTURE LIMIT CONTENT SCAL **GROUND WATER** LIMIT ▲POCKET PENETROMETER OQ CONTENT **OBSERVATIONS** VALUES NUMBER W 100 200 **DEPTH EVATION** AND REMARKS DESCRIPTION ELEV LNN DYNAMIC CONE PENETRATION X STANDARD PENETRATION TEST GRAIN SIZE DISTRIBUTION (%) GR SA SI CL metres WATER CONTENT (%) z 핍 10 20 20 30 40 SURFACE ELEVATION 263.50 40 60 kN/m 0.0 0.20 TOPSOIL: Black, silty sand, trace gravel, Stick up casing 263.30 trace organics, moist SS 6 Concrete SAND: Loose to compact, brown, sand, trace to some silt, trace gravel, moist SS 2 7 1.0 0 262.0 Becoming till-like with cobbles and 3¹ SS 28 Bentonite seal 4 SS 25 261 SS 5 26 0 4.0 258.9 Becoming grey, wet 6 SS 28 First water strike at 5.0 4.6 m 50 mm slotted pipe 258 Filter sand 6.0 SS 0 7 14 257.0 BOREHOLE TERMINATED AT 6.5 m Upon completion of augering Water at 4.6 m 7.0 No cave Water Level Readings: Date 2022-01-04 Depth 2.4 Elev. 261.1 2022-06-08 4.4 259.1 8.0 9.0 10.0 11.0 12.0 13.0 14.0 15.0 NOTES 1. Sample submitted for chemical testing



LOG OF BOREHOLE/MONITORING WELL NO. 108 1 of 1 17T 611496E 4910822N PROJECT Proposed Hewitt's Gate East Residential Development - Phase 3 PMI RFF 21BF052 LOCATION Barrie, Ontario BORING DATE December 14, 2022 **ENGINEER** FM **BORING METHOD** Continuous Flight Hollow Stem Augers TECHNICIAN FF SHEAR STRENGTH (kPa) **SAMPLES** SOIL PROFILE +FIELD VANE ΔTORVANE O Qu PLASTIC MOISTURE LIMIT MOISTURE SCAL **GROUND WATER** LIMIT ▲POCKET PENETROMETER OQ CONTENT STRAT PLOT **OBSERVATIONS** VALUES NUMBER W 100 150 **EVATION** AND REMARKS DESCRIPTION ELEV LNN DYNAMIC CONE PENETRATION X STANDARD PENETRATION TEST metres **GRAIN SIZE** WATER CONTENT (%) z DISTRIBUTION (%) GR SA SI CL 핍 10 20 30 SURFACE ELEVATION 263.75 20 40 60 40 kN/m 0.0 TOPSOIL: Black, sand, trace gravel, Stick up casing 0.30 trace organics, moist SS 7 Concrete SAND: Loose to compact, brown, sand, trace gravel, moist to very moist 2 1.0 SS 8 0 262.3 becoming gravelly and till-like 262 3¹ SS 5 Bentonite seal 4 SS 24 0 5 SS 24 0 259.8 CLAY AND SILT: Very stiff, grey, clay and silt, some sand, trace gravel, APL 6 SS 17 First water strike at 5.0 4.6 m 50 mm slotted pipe Filter sand TILL: Compact, grey, silty sand, some clay, some gravel, cobbles and possible 258.2 6.0 SS 7 25 257.3 BOREHOLE TERMINATED AT 6.5 m Upon completion of augering Water at 4.6 m No Cave Water Level Readings: Date 2022-01-04 Depth 3.3 Elev. 260.5 2022-06-08 3.8 260.0 8.0 9.0 10.0 11.0 12.0 13.0 14.0 15.0 NOTES 1. Sample submitted for chemical testing




LOG OF BOREHOLE/MONITORING WELL NO. 109 1 of 1 17T 610867E 4910652N PROJECT Proposed Hewitt's Gate East Residential Development - Phase 3 PMI RFF 21BF052 LOCATION Barrie, Ontario BORING DATE December 15, 2022 **ENGINEER** FM **BORING METHOD** Continuous Flight Hollow Stem Augers TECHNICIAN FF SHEAR STRENGTH (kPa) SOIL PROFILE **SAMPLES** +FIELD VANE ΔTORVANE O Qu PLASTIC MOISTURE APOCKET PENETROMETER O QU PLASTIC MOISTURE LIMIT CONTENT SCAL **GROUND WATER** LIMIT ▲POCKET PENETROMETER OQ CONTENT **OBSERVATIONS** VALUES NUMBER W **EVATION** 100 150 200 AND REMARKS DESCRIPTION ELEV HNN DYNAMIC CONE PENETRATION X STANDARD PENETRATION TEST GRAIN SIZE DISTRIBUTION (%) GR SA SI CL metres z WATER CONTENT (%) 핍 30 10 20 SURFACE ELEVATION 255.15 20 40 60 40 ιN/m 0.0 TOPSOIL: Black, sandy silt, trace gravel, 255 trace organics, moist 1 SS 8 0 CLAY AND SILT: Firm, brown, clay and silt, some sand, APL SS 2 7 1.0 TILL: Compact to dense, grey, silty sand, 3¹ SS some clay, trace to some gravel, cobbles and possible boulders, moist 2.0 4 SS 19 3.0 SS 5 18 6 SS 44 0 5.0 249.6 SAND: Dense, grey, sand, some silt, trace to some gravel, wet 6.0 SS 7 32 First water strike at 6.1 m BOREHOLE TERMINATED AT 6.5 m Upon completion of augering ARTESIAN CONDITIONS HIT Artesian conditions encountered 8.0 9.0 10.0 11.0 12.0 13.0 14.0 15.0 NOTES 1. Sample submitted for chemical testing





LOG OF BOREHOLE/MONITORING WELL NO. 110 1 of 1 17T 610819E 4910610N PROJECT Proposed Hewitt's Gate East Residential Development - Phase 3 PMI RFF 21BF052 LOCATION Barrie, Ontario BORING DATE December 15, 2022 **ENGINEER** FM **BORING METHOD** Continuous Flight Hollow Stem Augers TECHNICIAN FF SHEAR STRENGTH (kPa) SOIL PROFILE **SAMPLES** +FIELD VANE ΔTORVANE O Qu PLASTIC MOISTURE APOCKET PENETROMETER O QU PLASTIC MOISTURE LIMIT CONTENT SCAL **GROUND WATER** LIMIT ▲POCKET PENETROMETER OQ CONTENT **OBSERVATIONS** VALUES NUMBER W 100 150 200 **EVATION** AND REMARKS DESCRIPTION ELEV LNN DYNAMIC CONE PENETRATION X STANDARD PENETRATION TEST metres **GRAIN SIZE** WATER CONTENT (%) z DISTRIBUTION (%) GR SA SI CL 핍 10 20 30 40 SURFACE ELEVATION 256.80 20 40 60 kN/m 0.0 TOPSOIL: Black, sandy silt, trace gravel, Stick up casing trace organics, moist 1 SS 5 Concrete TILL: Loose, brown, sandy silt, some clay to clayey, trace gravel, very moist 2 SS 1.0 4 0 3¹ SS 2.0 <u>2.</u>1_ 254.7 Bentonite seal becoming compact, grey, silty sand, some clay, some gravel, cobbles and 4 SS 23 0 possible boulders 3.0 SS First water strike at 5 21 0 3.1 m SAND: Dense, brown, sand, trace to 252.8 some silt, trace gravel, wet 6 SS 30 5.0 50 mm slotted pipe Filter sand 6.0 SS 7 47 250.3 BOREHOLE TERMINATED AT 6.5 m Upon completion of augering Water at 3.0 m 7.0 No cave Water Level Readings: Date 2022-01-04 Depth 1.0 Elev. 255.8 2022-06-08 -0.6 257.4 8.0 9.0 10.0 11.0 12.0 13.0 14.0 15.0 NOTES 1. Sample submitted for chemical testing




LOG OF BOREHOLE/MONITORING WELL NO. 111 1 of 1 17T 610968E 4910803N PROJECT Proposed Hewitt's Gate East Residential Development - Phase 3 PMI RFF 21BF052 LOCATION Barrie, Ontario BORING DATE December 15, 2022 **ENGINEER** FM **BORING METHOD** Continuous Flight Hollow Stem Augers TECHNICIAN FF SHEAR STRENGTH (kPa) SOIL PROFILE **SAMPLES** +FIELD VANE ΔTORVANE O Qu PLASTIC MOISTURE APOCKET PENETROMETER O QU PLASTIC MOISTURE LIMIT CONTENT SCAL **GROUND WATER** LIMIT ▲POCKET PENETROMETER OQ CONTENT **OBSERVATIONS** VALUES NUMBER W 100 150 200 **EVATION** AND REMARKS DESCRIPTION ELEV LNN DYNAMIC CONE PENETRATION X STANDARD PENETRATION TEST GRAIN SIZE DISTRIBUTION (%) GR SA SI CL metres WATER CONTENT (%) z 핍 10 20 30 40 SURFACE ELEVATION 253.80 20 40 60 kN/m 0.0 TOPSOIL: Black, sandy silt, trace gravel, Stick up casing trace organics, moist SS 7 Concrete SAND: Loose to compact, brown, sand, trace to some gravel, trace silt, moist to 2 1.0 SS 13 Becoming gravelly 252.3 3¹ SS 15 252 Bentonite seal 251.7 CLAY AND SILT: Firm, grey, clay and silt, trace sand, APL First water strike at 4 SS 7 5 SS 7 0 250 TILL: Compact, grey, silty sand, some clay, some gravel, cobbles and possible boulders, moist 6 SS 24 249 5.0 50 mm slotted pipe Filter sand 248 6.0 SS 7 24 247.3 BOREHOLE TERMINATED AT 6.5 m Upon completion of augering Water at 2.2 m 7.0 No cave Water Level Readings: Date 2022-01-04 Depth 1.2 Elev. 252.6 2022-06-08 0.9 252.9 8.0 9.0 10.0 11.0 12.0 13.0 14.0 15.0 NOTES 1. Sample submitted for chemical testing









Geotechnical Investigation – Revision 1 Proposed Hewitt's South – Residential Subdivision Barrie, Ontario Project No. 2304675, December 18, 2023


Appendix D

Typical Details




Notes:


- Engineered Fill compacted to 100% Standard Proctor Maximum Dry Density (SPMDD) and inspected under the full time supervision of GEI.
- 2. Engineered fill must be placed in loose lifts of 200 mm or less and then compacted as noted above.
- Interior non-structural compacted fill compacted to 98% SPMDD with recommended part-time inspection.






ENGINEERED FILL PAD DIMENSIONING TYPICAL DETAIL







TYPICAL REINFORCED WALL






FOUNDATION WALL REINFORCING ON ENGINEERED FILL TYPICAL DETAIL







BASEMENT FOUNDATION WALL & SUBFLOOR DRAINAGE TYPICAL DETAIL





PAVEMENT DRAINAGE ALTERNATIVES
TYPICAL DETAILS