

GENERAL NOTES

- ALL MORKMANSHIP TO THE STANDARDS OF THE LANDSCAPE ONTARIO HORTICULTURAL TRADES ASSOCIATION AND THE CANADIAN LANDSCAPE STANDARDS.
- 2. ALL PLANT MATERIAL SHALL BE STAKED FOR LOCATION BY LANDSCAPE ARCHITECT AND CONTRACTOR
- 3. BACKFILL IS TO CONSIST OF SOIL NATIVE TO THE SITE OR GENERAL SOIL TYPE/CLASS NATIVE TO THE SITE. SOIL AMENDMENT MAY BE REQUIRED BASED ON SOURCE OF IMPORTED OR EXISTING SITE QUALITY OF TOPSOIL. PROVIDE NUTRIENT ANALYSIS OF TOPSOIL TO BE USED FOR LANDSCAPE PURPOSES IN ORDER TO DETERMINE SOIL AMENDMENT REQUIREMENTS.
- 4. ALL TREES SHALL HAVE AN EARTH SAUCER AT ITS BASE WITH A DIAMETER AS LARGE AS EXCAVATED AREA TO RETAIN MATER.
- 5. CONTRACTOR SHALL MAINTAIN ALL LANDSCAPE AREAS UNTIL OWNER'S ACCEPTANCE OF PROJECT.
- 6. UNLESS OTHERWISE STATED, ALL WORK SHALL CONFORM TO THE LANDSCAPE ONTARIO SPECIFICATIONS STANDARDS.
- 7. SPREAD MULCH TO A MINIMUM 75mm COMPACTED DEPTH ON ALL TREE PITS AND PLANTING BEDS.
- STAKING OF TREES SHALL BE AS PER DETAIL DRAWINGS PROVIDED. ALTERNATIVE METHODS MAY BE ACCEPTABLE WITH THE APPROVAL OF THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- 9. REPORT ALL DISCREPANCIES IN WRITING TO THE LANDSCAPE ARCHITECT.
- 10. CONTRACTOR TO LOCATE ALL UNDERGROUND UTILITIES.
- 11. PLANTING MAY BE ADJUSTED TO SUIT LOCATIONS OF SITE UTILITY STRUCTURES/SERVICES AND DRIVEWAYS.
- 12. SUBMIT A WRITTEN GUARANTEE TO THE EFFECT THAT ALL PLANTS ACCEPTED DURING THE PERIOD OF JANUARY 15t TO JULY 15th SHALL BE GUARANTEED UNTIL JULY 15th THE SECOND FOLLOWING YEAR. PLANTS ACCEPTED DURING THE PERIOD OF JULY 15th TO DECEMBER 31st SHALL BE GUARANTEED FOR TWO YEARS FROM THE DATE OF ACCEPTANCE. THE GUARANTEE PERIODS LISTED ABOVE SHALL APPLY TO ALL "NURSERY GROWN" PLANTS AS PER CITY OF BARRIE'S TWO YEAR MAINTENANCE REQUIREMENTS.
- 13. ALL MATERIALS TO BE APPROVED BY LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
- 14. CHECK AND VERIFY ALL DIMENSIONS AND QUANTITIES PRIOR TO COMMENCEMENT OF WORK. ANY DISCREPANCIES ARE TO BE REPORTED TO THE LANDSCAPE ARCHITECT. QUANTITIES NOTED WITHIN THE PLAN SUPERSEDE THOSE IN THE PLANT SCHEDULE. ANY SUBSTITUTIONS ARE TO BE APPROVED BY THE LANDSCAPE ARCHITECT.
- 15. PLANTING BEDS ARE TO BE MOUNDED A MINIMUM 75mm.
- 16. ALL GRADES NOT TO EXCEED 3:1 SLOPE.
- 17. SOD ANY AREAS MARKED WITH NURSERY SOD ON 150MM CLEAN TOPSOIL. FINE GRADE AND SOD ALL BOULEVARD AREAS TO MUNICIPAL SPECIFICATIONS AND REPAIR DAMAGE TO ADJACENT PROPERTIES, AS
- 18. FINAL INSPECTION AND ACCEPTANCE OF PLANTING WORK SHALL COINCIDE WITH THE FINAL INSPECTION AND ACCEPTANCE OF ALL WORK INCLUDED IN THE CONTRACT.
- 19. AT THE TIME OF FINAL INSPECTION, ALL PLANTS SHALL BE IN A HEALTHY, VIGOROUS GROWING CONDITION AND PLANTED IN FULL ACCORDANCE WITH DRAWINGS AND CONDITIONS.
- 20. ALL PLANTINGS AND HARD LANDSCAPE FEATURES ARE TO BE STAKED OUT ON SITE AND APPROVED BY THE LANDSCAPE ARCHITECT & THE CITY PRIOR TO INSTALLATION. ANY DEVIATIONS FROM THE APPROVED LANDSCAPE PLANS REQUIRE PRIOR CITY APPROVAL.

SIZE

250cm ht.

60mm cal.

60mm cal.

60mm cal.

60mm cal.

200cm ht.

300cm ht.

100cm ht.

50cm ht

50cm ht

150cm ht.

1 *G*al.

1 Gal.

Amelanchier canadensis

Acer campestre

Querca rubra

Pinus strobus

Thuja occidentalis

Euonymous alatus

Juniperus sabina

"Michita Blue"

Juniperus scopulorum

Hosta "Hadspen Blue"

Hosta "Golden tiara"

Juniperus chinensis 'Aurea

Gleditsia triacanthos

Pyrus calleryana "Glen's

CONDITION

Mire Basket

7 Gal. Pot

3 Gal. Pot

3 Gal. Pot

Mire Basket

No Substitution

No Substitution

55+ cm ht. - Blue Foliage

25+ cm ht. - Green/Yellow Foliage

- 21. SITE LIGHTING BY OTHERS.
- 22. BASE AND ENGINEERING INFORMATION PROVIDED BY PINESTONE ENGINEERING LIMITED.
- 23. IRRIGATION TO BE PROVIDED BY OTHERS.

8

4

13

69

125

Js

24. SEE ENGINEERING DRAWINGS BY PINESTONE ENGINEERING LIMITED.

Serviceberry

Hedge Maple

Shademaster Locust

TOTAL NUMBER OF TREES

TOTAL NUMBER OF TREES

TOTAL NUMBER OF SHRUBS

194 TOTAL NUMBER OF GROUND COVERS

Minged Burning Bush

Gold Coast Juniper

Savin Juniper

Plantain Lily

Plantain Lily

Upright Juniper

Chanticleer Pear

Red Oak

White Pine

White Cedar

UNIT AMENITIES:

BENCH (2) AND RECEPTACLE (1) (OR EQUIVALENT):

PARIS MANUFACTURING LTD. P.O. BOX 70, 21 SCOTT AVENUE PARIS, ONTARIO, N3L 3E5

BENCH MODEL: RSPS-6 RECEPTACLE MODEL: PSFT32

TREE GUARD

TORONTO FABRICATING & MFG. Co.

1021 RANGEVIEW RD. MISSISSAUGA, ONTARIO L5E 1H2

PRIOR TO INSTALLATION.

CELL: 705-441-4397

PH: 519-442-3324

GAZEBO

LIMESTONE TRAIL (OR EQUIVALENT) PH: 1-800-810-8223

FINAL LOCATION OF ALL SITE AMENITIES TO BE CONFIRMED WITH THE LANDSCAPE ARCHITECT ON SITE


CAP LIMESTONE ROCKERY:

QUANTITY: 4

LOCAL SUPPLIER (OR EQUIVALENT:

MAXWELL'S LANDSCAPE & MASONRY SUPPLY 9257 HWY 26 EAST COLLINGWOOD, ONTARIO, L9Y 3Z1 PH: 705-445-0111

REMARKS



REVISED PLANTING SPECIFICATIONS BY CITY MAY 23/18 MAR 12/18 REVISED AS PER NEW SITE PLAN AND CITY COMMENTS REVISED SITE PLAN DEC 20/17 FIRST SUBMISSION OCT 02/17 Date THE CONTRACTOR SHALL CHECK AND VERIFY ALL

Key Plan (n.t.s.)

PROPOSED CONIFEROUS TREE

PROPOSED DECIDUOUS TREE

PROPOSED SHRUB PLANTING

TREE/SHRUB DESIGNATION

TREE PROTECTION ZONE

EXISTING TREES TO BE RETAINED

PROPOSED 2m HIGH TIGHT

STAMPED ASPHALT REDDISH STAIN COLOUR

DETAIL BSD-1206 ON SHEET L-3)

Legend

DIMENSIONS AND REPORT ANY ERRORS OR OMISSIONS TO THE CONSULTANT BEFORE COMMENCING OR PROCEEDING WITH ANY MORK.


DO NOT SCALE THIS DRAWING

Advancing Sustainable Development Solutions Group 372 Peel St, Collingwood, Ontario, L9Y 3W4 Phone: 705-443-8394 Fax.: 705-443-8494

> 521, 527, 531 Big Bay Point Road Barrie, Ontario

LANDSCAPE

PLAN



	1:150	
Date:	Oct 2017	
CAD File:	HDG-BBP-L1_R3	
Drawn by:	C.M.	

Checked by:

M.H.

ALL DRAWINGS REMAIN THE PROPERTY OF THE LANDSCAPE ARCHITECT AND SHALL NOT BE REPRODUCED OR REUSED WITHOUT THE LANDSCAPE ARCHITECT'S WRITTEN

THIS DRAWING SHALL NOT BE USED FOR CONSTRUCTION OR TENDER PURPOSES UNLESS SIGNED AND DATED BY MICHAEL J. HENSEL, OALA CSLA, LANDSCAPE ARCHITECT,

Michael J. Hensel, OALA, CSLA

HENSEL DESIGN GROUP INC., ONTARIO (705-443-8394)

DATE

SHEET 1 OF 3